NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

COLD AIR SOLUTIONS
Pune

Project, Location :

Date : 15.09.2021
Quote NO : SQA.21.22.0163 R
Kind Attn : Nitin Patkar
Email Id : nitinpatkar08@gmail.com
Contact No: 9545556049

Subject : Revised quotation for Rapid Roll-UP Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Rapid Roll-UP Door (100% Imported component aseembled in India)**	2000	2500	1	285,000	285,000	15,000	15,000
2	**Microwave Radar Sensor**			1	20,000	20,000		-
	Total			**1**		**305,000**		**15,000**
				Supply + Installations				**320,000**
				P&F Charges	2%			6,400
				Total Without Taxes				**326,400**
				GST Extra @ 18%	18%			58,752
				Total With Taxes				**385,152**
				Transportation Charges		**Extra at atcual**		
				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

High Speed Door - 100% Imported

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



Sr. No	Description	Specifications
1	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking .
2	Opening speed	upto 3 m/s
3	Closing speed	0.8 m/s
4	Control Panel	4 Push Button operated
5	Security Features	EN 13241-1 Standard
6	Resistance to wind load	EN12424 upto class 1
7	Curtain	Fabric Non-Transparent PVC section & One View Transparent PVC window on eye level in door to see other side minimum size of view glass is 700x500mm
8	PVC Curtain	RAL Blue PVC Fabric 2mm thikness
8	Guide Material	Aluminum
9	Hood Cover	GI
10	Motor Cover	GI
11	Operator & Control	German Direct drive Motor
12	Connecting Voltage	230V , 1Ph , N
13	Open-Stop-Close Button	Standarad
14	Protection Category (Operator/Control)	IP 54 / IP 65
15	Power Consumption	0.75 kw Motor
16	Emergency Off Button	Standard
17	Closing Zone Monitoring	Optical Safety edge
18	External Route Monitoring	Photocell
19	Emergency Opening	EMG opening through Crank Handle
20	Microwave Radar	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Pradeep Shinde
8551096333
For NIHVA Technologies Pvt Ltd