NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Architects united
111/9, 14th Lane, Prabhat Road,
pune - 411 004.
Maharashtra -India.

Date : 14.08.2019
Quote NO : SQT.19.20.1817R
Kind Attn : Ms. Vasundhara
Email Id : au@architectsunited.co.in
Contact No: +91 20 2544 1426

Project Name & Location: Talegaon Industrial Parks Pvt Ltd

Subject : Revised Quotation for Dock Leveler, Rolling Shutter, Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**NIHVA Dock Leveler Capacity 6 Ton**	2000	3000	370	202,000	74,740,000	5,000	1,850,000
				Total		**74,740,000**		**1,850,000**
2A	**Option 1 : Gear Operated Rolling Shutter**	2400	3000	370	47,000	17,390,000	5,000	1,850,000
2A	**Option 1 : Gear Operated Rolling Shutter**	4000	5000	44	102,000	4,488,000	5,000	220,000
				Total		**21,878,000**		**2,070,000**
2B	**Option 2 : Motorised Rolling Shutter**	2400	3000	370	59,000	21,830,000	5,000	1,850,000
2B	**Option 2 : Motorised Rolling Shutter**	4000	5000	44	124,000	5,456,000	5,000	220,000
				Total		**27,286,000**		**2,070,000**
2C	**Option 3 : Automatic Sectional Doors**	2400	3000	370	227,000	83,990,000	10,000	3,700,000
2C	**Option 3 : Automatic Sectional Doors**	4000	5000	44	298,000	13,112,000	10,000	440,000
				Total		**97,102,000**		**4,140,000**
4	P&F Charges					**NIL**		
	Total Without Taxes							
	GST Extra @ 18%							-
	Total With Taxes							**-**
5	Transportation Charges					**Included in above Prices**		
6	Unloading Charges @ Site					**Included in above Prices**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA Dock Leveler

Sr. No	Description	Specifications For 6 Ton
1	Model No	NDL20256T
2	Make	NIHVA
3	Required Capacity	6 Ton
4	Hydraulic Power pack	1 HP, 3PH
5	Control Panel	4 Push Button operated
6	Deck operation	By push button Deck UP & Deck Down
7	Lip operation	By push button Deck UP & Deck Down
8	Loading platform height from road Level	4 feet (1200 mm)
9	Travel above from Dock level height	350 mm
10	Travel below from Dock level height	200 mm
11	Deck platform size	2000mm (W) x 3000mm (L)
12	Lip sizes	400 mm
13	Clear Pit dimensions	2040mm (W) x 3000mm (L) x 485mm (H)
14	Drive type	Direct by electric Motor
15	Power Consumption	0.75 kw Motor
16	Degree of protection for motor	IP 55
17	Motor RPM	1410 rpm
18	Pump design flow	1.8 LPM
19	Pump pressure	200 bar
20	Safety valve set pressure	90 bar
21	Pump type	Gear
22	In built safety valve	Yes
23	Volume of oil receiver	8 Ltr
24	No of Deck Cylinders	2 Nos
25	Deck Plate Thickness	8 mm Chequered Plate
25	No of Lip Cylinders	1 No
25	Lip Plate	16 mm Thick Plate
26	Dock Bumpers	1 Pair included

NIHVA Rolling Shutter

Sr. No	Description	Specifications
1	Model No	NRS00123
2	Rolling Shutter	Motorised Rolling Shutter with Mild Steel of thickness of 1 mm.
3	Mounting Location area	Inside area / Outside area
4	Curtain Panel	The panel made of 1.0mm thick MS steel
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting -Jielong

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY Sectional Door

Sr. No	Description	Specifications
1	Model No	Crawford Brand
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Vertical
4	Door produced Based on which certification	Doors produced according to ISO 9000 or ISO 14000 certified.
5	Opening/Closing Speed	0,28 m/s
6	Door Material	GI Steel
7	Panel Thickness	42mm
8	Panel colour	RAL 9002 Powder coated
9	External surface of the panel	diamond grid design with a glossy finish at the section joints.
10	inside surface of the panel	Monolithic surface on the inside of the door
11	Broken cold bridge	Section joints with broken cold bridges
12	Panels are euipped with ?	Panels to have integrated steel reinforcement for fixation of hinges and hardware.
13	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
14	All Panel height	All panels should be 545mm high
15	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.
16	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.
17	Steel component Material	All steel components to be electro galvanized
18	Hinge Material	Glass fibre reinforced Polyamide
19	Spring Material surface finish	Powder coated
20	Spings transport till plant	Pre tensioned spring package
21	Water Penetration	EN 12425 class 3
22	Air Permealibity	EN12426 class 3
23	Wind Load	EN21424 class 3
24	Thermal Transittance	EN 12428 1.10W /m2K
25	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
26	Door saftey device 1	Doors equiped with spring break device
27	Door saftey device 2	Door equiped with pneumatic safety edge
28	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts protuding from a moving door
29	Incase of Power failuer	Doors to be equiped with quick release fuction
30	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
31	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
32	Emergency Operation	by Disengagement rope manual
33	Operating Switch	Up/Down Keypad + stopbutton
34	Environmental Green Product Declaration Certification	as per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks for Dock Leveler & Rolling Shutter, 11-12 Weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd