NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1422 **Date:- 29.05.2019**

Gulbrandsen Technologies (India) Pvt Ltd
405, Synergy Square,405, Synergy Square,
Krishna Industrial Estate, Gorwa,
Vadodara - 390016, Gujarat -India

Kind Attn: Mr. Sanket Phadnis
Email: sphadnis@gulbrandsen.com
Contact No: (898) 001-1984

Project Name And Location :Gulbrandsen Technologies (India) Pvt Ltd, Vadodara

Subject : Quotation for NIHVA ASSA ABLOY (Albany) RR392 and ASSAABLOY (Albany) HS9020G

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**High Speed Door ASSAABLOY (Albany) HS9020G (100% Imported products from Europe)**				
Operating speed	Opening: up to 1,2 m/s 2, closing: 0,5 m/s .The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.				
Wind load resistance,	Class 1 (300 N/m2), maximum wind load while closing 50 N/m2				
Techncial details	a. The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage. b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself. c. Vision Window - One row of 400 mm height.				
1	**Size: (W) 2000 mm X (H) 2200 mm (Supply + Installation)**	3	No	469,000	1,407,000
1	**Size: (W) 3000 mm X (H) 3300 mm (Supply + Installation)**	2	No	568,000	1,136,000
2	**Interlocking**	1	No	18,000	18,000
3	**Loop Detector**	1	No	36,000	36,000
	Total				**2,597,000**
B	**ASSA ABLOY-ALBANY Rapid Rollup Door RR392 (100% Imported with all components – made in Germany)**				
Construction:	High-Speed Roller Door with transparent curtain and blue (similar RAL 5002) reinforcement stripes, optional red (similar RAL 3002). Door with curtain tension.				
Drive Unit:	motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Control system:	MCC Frequency converter for opening/closing speed up to 2,2 / 0,9 m/s.Power supply required 3L(N)PE 400/415 V, 50 Hz. Protection IP 55.				
Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.				
Safety features:	Safety contact edge, Safety photocell transmitter / receiver inside side columns.				
Hood Cover	GI Cover				
Motor Cover	GI Cover				
Emergency Operation	By Hand Crank				
1	**Size: (W) 3000 mm X (H) 3000 mm (Supply + Installation)**	1	No	785,000	785,000
	Total				**785,000**

GST Pune	27AAECN0437H1ZM

Total	**3,382,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Electrical connection for control panel.

Client Scope

1 Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	8 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm purchase order & balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain** on - 8551092333. For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd