NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1737 **Date : 21.06.2018**

Alpha Automation
Goa

Kind Attn: Mr. Rinaldo
Email: rinaldo081992@gmail.com
Contact No: 8668549621

Project Name And Location :

Subject : Quotation for High Speed Door HS9020G

Dear Sir,
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount Euro
A	**High Speed Door** **ASSAABLOY (Albany) HS9020G** **(100% Imported products from Europe)**				
Operating speed	Opening: up to 1,2 m/s 2, closing: 0,5 m/s .The fast opening and closing speed improves your traffic flow, provides employee comfort, and saves energy.				
Wind load resistance,	Class 1 (300 N/m2), maximum wind load while closing 50 N/m2				
Techncial details	a. The soft bottom edge has no rigid parts, it moulds around any obstruction to prevent injury or damage. b. When an object hits the door, the fabric curtain absorbs the impact and releases itself from its side guides without causing damage or being damaged itself. c. Vision Window - One row of 400 mm height				
1	Size: (W)1200 mm x (H) 1500 mm (Supply + Installation)	1	No	443,000	443,000

GST Pune :	27AAECN0437H1ZM	**TOTAL BASIC AMOUNT**	**443,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes:**	:	Extra as applicable + Taxes
3	**Delivery**	:	9 -10 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
4	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch
5	**Insurance**	:	Extra As applicable
6	**Tax**	:	GST @ 18% Extra
7	**Validity**	:	Validity of Offer is 15 days from the date of quotation
8	**Warranty**	:	12 months from the date of supply

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti.
7219206333
For NIHVA Technologies Pvt Ltd