NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JSW Steel Coated Products Ltd.
Kalmeshwar,
Maharashtra
India

Date : 30.09.2019
Quote NO : SQT/19-20/2099
Kind Attn : Mr. Rajesh Dhote
Email Id : dhote.rajesh@jsw.in
Contact No: 9860269737

Subject : Quotation for Sectional Door, Rolling Shutter and Sliding Door. (Project - JSW Kalmeshwar ,New Shed of CCL-3.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2,3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorized Rolling Shutter	4000	4000	1	1,16,000	1,16,000	20,000	20,000
2	MS Motorized Rolling Shutter	7000	5000	1	2,19,000	2,19,000	20,000	20,000
3	MS Motorized Rolling Shutter	4000	6000	3	1,64,000	4,92,000	20,000	60,000
4	Grill Motorized Rolling Shutter	5000	4500	3	1,59,000	4,77,000	20,000	60,000
5	Sectional Door	7000	6000	8	5,31,000	42,48,000	20,000	1,60,000
6	Sectional Door	4000	4000	1	3,13,000	3,13,000	20,000	20,000
7	Sliding Door	3000	3000	1	2,40,000	2,40,000	20,000	20,000
				Total		**61,05,000**		**3,60,000**
8	P&F Charges			3%		1,83,150		
	Total Without Taxes					62,88,150		3,60,000
	GST Extra @ 18%			18%		11,31,867.00		64,800
	Total With Taxes					**74,20,017**		**4,24,800**
9	Transportation Charges					In Client Scope		
10	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sectional Door

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	Door type	1042P	
2	Opening Direction	90 Degree	
3	Type of Mounting	High Lift	
4	Door produced Based on which certificatio	Doors produced according to ISO 9000 or ISO 14000 certified processes	
5	Opening/Closing Speed	0.25 m/s	
6	Door Material	GI Steel with PUF inside	
7	Panel Thickness	42mm	
8	Panel colour	RAL 9002 Powder coated	
9	External surface of the panel	diamond grid design with a glossy finish at the section joints.	
10	Inside surface of the panel	Monolithic surface on the inside of the door	
11	Broken cold bridge	Section joints with broken cold bridges	
12	Door sealent	All door sealants made of EPDM rubber.	
13	All Panel height	All panels should be 545mm high	
14	Panel Inside insulation metrial	Insulation material to be CFC free polyuretane foam.	
15	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.	
16	Steel component Material	All steel components to be electro galvanized	
17	Hinge Material	Glass fibre reinforced Polyamide	
18	Panel Thickness	42 mm	
19	Spring Material surface finish	Powder coated	
20	Water Penetration	EN 12425	class 3
21	Air Permealibity	EN12426	class 2
22	Wind Load	EN21424	class 3
23	Thermal Transittance	EN 12428 1.10W /m2K	
24	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
25	Door saftey device 1	Doors equiped with spring break device	
26	Door saftey device 2	Door equiped with pneumatic safety edge	
27	Door saftey 3	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts	
28	Incase of Power failuer	One can operate the Door manually	
29	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
30	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft	
31	Emergency Operation	By Disengagement rope manual	
32	Operating Switch	Up/Down Keypad + stopbutton	
33	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804	

MS Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	Description	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of MS Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Sliding Door

Sr .No.	Specification	Automatic Sliding Door
1	Description:	ASSA ABLOY-BESAM-Automatic Sliding Door SL 500 (100% imported from Sweden)
2	Operator type	Program Selector PSK-6U
3	UPS	Included
4	Open Operator lock	No lock.
5	Surface Treatment	Silver Anodized
6	Bottom Profile	12 mm tempered glass
7	Aluminium Sheet	40x40x2mm MS SQ. TUBE

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat on 7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd