NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Mahindra Electric
Talawade Chakan Rd, Pune - 410504

Project, Location :

Date : 30.01.2021
Quote NO : SQT.20.21.2995
Kind Attn : Ashutosh Rathor
Email Id : rathor.ashutosh@mahindra.com
Contact No: 8600900858

Subject : Quotation for Manual Sliding Single Leaf Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Manual Sliding Single Leaf Door**	1500	2500	2	98,000	196,000	10,000	20,000
2	**Manual Sliding Single Leaf Door**	2000	2500	8	110,000	880,000	10,000	80,000
3	**Manual Sliding Single Leaf Door**	3000	2500	3	170,000	510,000	10,000	30,000
	Total			**13**		**1,586,000**		**130,000**
4	P&F Charges			3%		47,580		
	Total Without Taxes					1,633,580		130,000
	GST Extra @ 18%			18%		294,044.40		23,400
	Total With Taxes					**1,927,624**		**153,400**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Manual Sliding Single Leaf Door

Sr. No	Description
1	Door for positive application uptill +2 degree.
2	PUFF Insulation 45kg
3	PCGI sheet thickness 0.6mm
4	80mm door thickness, with C-flushing, wall frame.
5	Locking arrangement along with emergencyrelease system, with one number view port.
6	off white color, with door frame.
7	Provision for autoation in future with extended track and heavy duty reinforcement.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 2 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd