NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/19-20/1850 **Date 29.07.2019**

Address
Dolpin Offshore india pvt ltd

Kind Attn: Mr.Chandan Kumar
Email ID: c.kaushik28@gmail.com
Contact No: 9500067162

Project Name And Location : Mumbai

Subject : Quotation for Chain Conveyor.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions. This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Chain Conveyor**				
	Component to convey : LPG Cylinder **Size of the component: D315 x 825 mm height** **Weight of product :19 kg** **Capacity : 65 kg / metre** **Total Length : 20000 mm** **Width : 350mm** **Height : 1500 mm** **Speed : 25 mtr / min** **Include Following -** **• Mechanical Structure** **• Machining Components** **• Mechanical Bought out** **(flange mounted bearing ,Drive & Driven Sprocket , Chain)** **• Electrical Bought out** **(Drive Motor[Flame proof] , Control Panel , Sensors , VFD)**				
1	Size (W) 350mm x (L) 20000 mm x (H) 15000 mm [Supply +Installation]	1	No	8,25,000	8,25,000
				Total	8,25,000

GST Pune	27AAECN0437H1ZM

Grand Total	8,25,000

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Civil/structural changes required on site is in client's scope.
3. Electrical Supply on the site single phase/three phase points at different places.
4. Provide electrical cables near to the installation machinery
5. Fork lift/crane to be provided if required .
6. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement.
2. Billing will be as per the supply of material ,not as per site measurements
3. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	5-6 weeks from the date of receipt of confirmed purchase order, Advance
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply .

Please feel free to Contact **Mr. Arjun Patil** on +91-8551096333 For any further Clarification /Information in this Concern.

With Best Regards
Pradip
7709586333
For NIHVA Technologies Pvt Ltd