NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1815R1 **Date:- 05.03.2020**

KIRPEKAR ENGINEERING PVT LTD.
PLOT 8A RAISONI INDUSTRIAL PARK MIDC PHASE 2
HINJAWADI PUNE 411057.

Kind Attn: Mr. Balaji
Email: purchase@kirpekarengg.com
Contact No: 9028874633

Subject : Revised Quotation for Machine Protection Door RP300

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Albany Rapid Rollup Door RP300 (100% Imported with all components – made in Germany)**				
Construction:	Curtain RollTexPlus (silicone-free) which is specially designed for Robotics welding application without vision window, according to the following RAL colours: blue (RAL 5002)				
Side frames:	Aluminum anodized two parts, to have easy access to switches and service.				
Drive Unit:	Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Control system:	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box painted (RAL 7035) with Up-Stop-Down buttons.				
Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.				
Safety features:	Safety edge with cable chain integrated in side frames				
Safety limit switch:	1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.				
1	Size: (W) 1000 mm X (H) 1200 mm	1	No	525,000	525,000
2	Installation charges for above door	1	No	17,000	17,000
				Total	**542,000**

GST Pune	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	Nill
3	**Freight Notes**	:	Extra As applicable
4	**Delivery**	:	10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% advance along with confirm purchase order balance 20% before dispatch
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST@18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat** on - 7410169333 For any further Clarification /Information in this Concern.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd