NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Home Zone Stainless Pvt Ltd
Vasai, Mumbai

Date : 02.10.2021
Quote NO : **MHE_21.22.0034R**
Kind Attn : Mr. Pratik Patil
Email Id : maintenance.pratik@hzspl.in
Contact No: 8554811861

Project Name & Location: Home Zone Stainless Pvt Ltd, Vasai

Subject : Quotation for Telescopic Belt Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor (Total length 6 mtr)**	**1**	**9,50,000**	**9,50,000**	**25,000**	**25,000**
		Total		**9,50,000**		**25,000**
	P&F Charges	3%		**28,500**		
	Total Without Taxes			**9,78,500**		**25,000**
2	GST Extra @ 18%	18%				**Extra At Actual**
3	Transportation Charges					**Extra At Actual**
4	Insurance					**Extra At Actual**
5	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Material To Be Handle	Gunny Bags (Jute Bags or Goni)
2	Weight Of Bags	50 Kg
3	Size of Box/Bags (Max)	250mm (H) X 400mm (W) X 400mm (L)
4	Capacity	100 Bags per hr
5	Type	Movable
6	Belt Width	600 mm
7	Type Of Belt	PVC Belt
8	No. of Extension Stages	3
9	Fixed Length	3000 mm
10	Telescopic Length	3000 mm
11	Total Length	6000 mm
12	Height Of the conveyor	600 mm
13	Height Adjustment required	Yes
14	Panel make	NIHVA make
15	Painting /Powder coating	RAL (Please specify)
16	Max./Min.height of conveyor(Inclination)	45 deg
17	Electric component make	Siemens
18	MOC of conveyor	MS powder coated/Painted
19	Sensor make(Omron/P&F/Sick/etc)	Omron
20	Belt Motor make	Forbo
21	Belt Gear box make	SEW/Bonfiglioli/PBL
22	Type of Gear Box (Worm/Helical)	Worm
23	Movement(Forward/Reverse/Both)	Both
24	Mode of lifting(Electric/Hydraulic)	Hydraulic
25	Max Height to lift	1500 mm

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of Confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50% against readiness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Vijay Tarak on 8551093333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd