NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Suroj Buildcon Pvt Ltd.
Bungalow No. 3, Liberty Society Phase-I,
North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

Date : 11.01.2020
Quote NO : SQT/19-20/2841R2
Kind Attn : Nagesh Jeure
Email Id : njeure@suroj.in
Contact No: 7709757563

Subject : Quotation for Rolling Shutter.(Project Location -Jhagadia, Gujarat)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**G I Motorised Rolling Shutter**	3000	4000	1	133,000	133,000	12,500	12,500
2	**G I Motorised Rolling Shutter**	3000	2800	1	111,150	111,150	12,500	12,500
3	**G I Motorised Rolling Shutter**	2500	3500	2	114,000	228,000	12,500	25,000
4	**G I Motorised Rolling Shutter**	2500	3450	1	113,050	113,050	12,500	12,500
5	**G I Motorised Rolling Shutter with Perforation of 600 mm**	2500	3000	1	108,300	108,300	12,500	12,500
				Total		**693,500**		**75,000**
6			P&F Charges	3%		20,805		
			Total Without Taxes			714,305		75,000
			GST Extra @ 18%	18%		128,574.90		13,500
			Total With Taxes			**842,880**		**88,500**
7			Transportation Charges			Extra at actual		
8			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	G I Motorised Rolling Shutter
1	**Description:**	G I Motorised Rolling Shutter with G I Laths with thickness of 1.2 mm
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover and Motor Cover**	Hood Cover made of GI Sheet Thickness 2.6 mm as per BOQ and Motor Cover
12	**Surface finish**	Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection
14		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd