NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

M/S Counter Steel
Pune

Date : 11.11.2020
Quote NO : SQT.20.21.2822
Kind Attn : Mr. Maruti Kharmute
Email Id : Maruti.kharmute1984@gmail.com
Contact No :

Project Name & Location: Talegaon Project

Subject : Quotation for Rolling Shutter,Dock Leveller, Sliding Gate, Boom Barrier etc.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**M S Motorised Rolling Shutter**	3000	4000	1	100,941	100,941	15,000	15,000
2	**M S Motorised Rolling Shutter**	3000	3500	1	93,838	93,838	15,000	15,000
3	**M S Motorised Rolling Shutter**	4000	6500	7	184,882	1,294,174	15,000	105,000
4	**M S Motorised Rolling Shutter**	4000	4000	1	125,765	125,765	15,000	15,000
5	**M S Motorised Rolling Shutter**	5000	6000	1	203,824	203,824	15,000	15,000
6	**NIHVA make Dock Leveller**	2000	2500	7	210,000	1,470,000	15,000	105,000
7	**Motorised Sliding Gate**	4500	1500	1	327,250	327,250	15,000	15,000
5	**Motorised Sliding Gate**	6000	1500	1	358,000	358,000	15,000	15,000
6	**Motorised Sliding Gate**	9000	1500	2	419,156	838,312	15,000	30,000
a)	**Manual Wicket Gate**	1500	1500	1	35,000	35,000	10,000	10,000
7	**Boom Barrier - 6 Mtr**			4	110,000	440,000	12,000	48,000
8	**Boom Barrier - 4 Mtr**			4	110,000	440,000	12,000	48,000
				Total		**5,727,104**		**436,000**
9			P&F Charges	3%		**171,813**		
			Total Without Taxes			**5,898,917**		**436,000**
			GST Extra @ 18%	18%		1,061,805		78,480
			Total With Taxes			**6,960,722**		**514,480**
9			Transportation Charges			**Extra at Actual**		
10			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

M S Motorised Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection

Nihva Make Dock Leveller

Sr. No	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 safe working height(+900 mm) / (-) 250 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Overall length	3000mm + Lip Length (400mm)
11	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 3000 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Structure	Included
23	Maximum slope can be achieved	10%
24	Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

Boom Barrier

Sr. No.	Description	Specifications
1	Size	4/6 Meter
2	Model No	Michealangelo 60
3	Opening Time	6 S
4	Slowdown	Adjustable
5	Motor Power Supply	24 V
6	Type of limit Switch	Electronic
7	Frequency of Use	Continuous Use
8	Protection Rating	IP54
9	Lock	Mechanical

Motorised Single Leaf Sliding Gate

Sr. No.	Description	Specifications
1	Opening Direction	Horizontal - from left to right or reverse
2	Mounting Location area	Inside area
3	Design Pattern	Standard Tubular Design Pattern
4	OUTER TUBE	72 x 72 x 3.2mm MS SQ. TUBE
5	FOR POST	72 x 72 x 3.2mm MS SQ. TUBE
6	INNEAR TUBE	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
7	Gap Between Tubes	125mm
8	Bottom Rail on ground	Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	Guide Rollers supporter during Gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of
11	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
12	El motor make	BFT – Italy (100% imported)
13	Emergency Operation	Manual after turn the switch
14	Operating Switch	Push Button from inside
15	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: **Please find below List which are in Client Scope**

Sr. No	**Description**
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil structural work required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 4 -5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 40% Advance along with Confirmed Purchase Order & Balance against readyness of material before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333 .**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd