NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

General Mills Kind Attention: Mr. Naresh Jadhav
F- 11 , M.I.D.C., Malegaon, Tal - Sinner
Nasik - 422113

Date : 07.09.2019
Quote NO : SQT.19.20.2031
Kind Attn : Mr. Chandrabhan
Email Id : Chandrabhan.sangale@genmills.com
Contact No: 9881700268

Project Name & Location:

Subject : Quotation for Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option 1							
1	**NIHVA Scissor Lift Capacity : 1.5 ton**	1500	1500	1	554,600	554,600	20,000	20,000
	Option 2							
2	**NIHVA Scissor Lift Capacity : 1.5 ton With manual rotating platform**	1500	1500	1	665,627	665,627	20,000	20,000
				Total				
3	P&F Charges			3%	-			
	Total Without Taxes				-		-	
	GST Extra @ 18%			18%	-		-	
	Total With Taxes				-		-	
4	Transportation Charges				**In Client Scope**			
5	Unloading Charges @ Site				**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Option 1: **NIHVA Scissor Lift**

Sr. No	Description	Specifications For 6 Ton
1	Capacity	1.5 ton
2	Platform size	1500L x 1500W
3	Shut ht	450 mm
4	Max ht	1950 mm
5	Lift above Floor Level	1500 mm
6	Power pack	3HP,3PH
7	Safety bellow from all side	
8	Safety railing 900 mm height on platform only length side. (Two loading /unloading side open)	
9	Safety cage railing with door on floor 1000 mm height interlocking with scissor lift.	
10	MOC for Top cheq. Sheet & railing on platform is SS304 remining in mild steel.	
11	As discussed we provide 7 stops in lifting height.	
12	Color : powder coated with approved RAL color.	

Option 2: **NIHVA Scissor Lift with Manual Rotating Platform**

Sr. No	Description	Specifications For 6 Ton
1	Capacity	1.5 ton
2	Platform size	1500L x 1500W
3	Shut ht	550 mm
4	Max ht	2050 mm
5	Lift above Floor Level	1500 mm

Remaining Specifications are same as above

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks for Dock Leveler & Rolling Shutter, 11-12 Weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd