ASSA ABLOY

Installation Conditions

1. Continuous uninterrupted access to any single door section or as agreed.

2. A clear floor area of 4 meters each side of the door centerline must be available during the door leaf fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

   The temporary floor material must be smooth and flat and also have the possibility to take the weight and wheel pressure of our lifting equipment as scissor lifts, boom lifts, tele handlers and fork lifts. Surrounding ground, counted from the door opening, must also have the possibility to take the weight and wheel pressure of mentioned types of lifting equipment. That condition shall also apply for a mobile crane in those cases a mobile crane shall and/or must be used during the installation.)

3. 380/400/415V 3 phase power supply to be hard wired directly to the Megadoor Main panel. If not available at the start of installation, a temporary supply is acceptable. Voltage/Hz as appropriate to country. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate. Power must be available around the clock during the entire installation.

4. A wheel loader with forks, tele handler with forks or a forklift is to be supplied (by others) for offloading the goods upon delivery. The customer/main contractor are responsible for unloading the goods, if no other agreement has been arranged with ASSA ABLOY Entrance Systems (AAES)

5. A suitable door frame should be available designed in accordance with final approval drawings issued by AAES. Tolerances/deflections of the support structure to be in accordance with the drawings.

   A suitable structure should be available together with mullion floor pits (multiple section doors only) designed in accordance with final approval drawings issued by AAES. Tolerances/deflections of the support structure to be in accordance with the drawings. Mullion pit angles (100x100x10) supplied by others to ASSA ABLOY Entrance Systems design.

6. Provision of 110/220/230 Volt power supply (by others) for hand tools and battery charge of equipment as lifts etc. Voltage/Hz as appropriate to each country's regulations. Power must be available around the clock during the entire installation.

7. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

8. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation schedule may require amending.

   Programme and budget based on 10 working hours (7 am to 5 pm) 6 days a week.
   If this is not possible the installation programme and rates may require amending.

9. Any storage costs for materials due to delays outside of AAES control will be charged to the main contractor.

10. The programme assumes fair weather working between the months of March and October and does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the opportunity to claim extensions of time and associated costs for exceptionally adverse weather.

ASSA ABLOY Entrance Systems Production Skellefteå AB

PO Box 383
SE-931 24 Skellefteå
Registration number: 556059-9523

Phone: +46 10 47 48 554

Web: www.megadoor.com
Web: www.assaabloyentrance.com

ASSA ABLOY

Installation Conditions

11. Any waiting time incurred by our engineers due to circumstances outside of their control, will be charged for at the appropriate hourly rate (see day work rates).

12. Day work Rates & Waiting time

    Labour: €80/hour per man.
    Hotel & Subsistence per Diem: Cost.
    Materials: Cost plus 30%.
    Plant: Cost plus 25%.

13.

13. We assume access to toilet facilities, drinkable fresh water, shower, kitchen, close to the installation site. And that all facilities shall be heated and ventilated as well have Air Condition equipment during very hot periods.

14. Health & medical treatment must be available nearby installation site. ASSA ABLOY teams are protected by normal travel insurance. If extra insurance is necessary then this is not included.

15. The installation site must be protected against theft, sabotage and fire by means of guards and/or fences and enclosure and a fire brigade. Guards, fences and enclosure will also be needed to prevent that non authorized visitors shall enter the installation site and be injured by material and machines. Guards, fences, enclosure and fire brigade by others.)

16. Collecting and deposition of all kind of Waste Material shall be done by others.

17. As part of the installation process we are required to use to following machines, Arc welding equipment, grinders and drilling machines. Unrestricted access for their use is required and it is accepted that "Hot works permits" may be mandatory before the use of this equipment.

18. We have included for a working foreman, who will be responsible for onsite safety. No allowance has been made for any non-productive permanent on site supervision or banks man, refer to standard risk and method statements.

19. Final clean of the door leafs is by others and no cost for this has been included

20. Installation price included in the quote is based on the fact that all doors in the contract can be installed with one mobilization. If there is a need for extra mobilization, this price is not included in and will be quoted separately.

IMPORTANT NOTE FOR THE MAIN CONTRACTOR

It is important that the following timescales are taken into account, with regard to placement of an order and interface with other trades, when compiling the overall construction schedule. The floor slab should be finished, or at least an area of 4m each side of the door line and the wall/roof cladding should be completed to the door end of the building.

AAES is entitled to suspend installation if the performance of its obligations, due to weather conditions or otherwise, would be in breach of any applicable security regulations. ASSA ABLOY Entrance Systems shall not be held responsible for delays in relation to the installation time plan due to such suspensions (and consequently not be liable for any liquidated dames or the like).