NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tasty Bite Eatables Limited
490, Bhandgoan, Pune 412 214

Date : 19.12.2019
Quote NO : SQT/19-20/2308
Kind Attn : Mr.Terence D'Cruz
Email Id : terence@tastybite.com
Contact No: 8888853116

Subject : Quotation for Sectional Door , Cold Room Door and High Speed Door.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Cold Room Door**	2500	3500	2	462,000	924,000	20,000	40,000
2	**High Speed Door (HS 9020G)**	2500	3500	1	511,000	511,000	20,000	20,000
3	**Sectional Door**	2400	3000	1	251,000	251,000	20,000	20,000
				Total		**1,686,000**		**80,000**
4	P&F Charges			3%		50,580		
	Total Without Taxes					1,736,580		80,000
	GST Extra @ 18%			18%		312,584.40		14,400
	Total With Taxes					**2,049,164**		**94,400**
5	Transportation Charges					In Client Scope		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

A) Technical Specification **Cold Room Door**

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy
1	**thickness**	120 mm
2	**Density**	42kg/m3 with 0.6 mm PPGI
3	**ALU. Wall Frame**	3.5 mm thick
4	**Rollers**	The rollers are made of POM (nylon).
5	**Heating Arrangement:**	Supplied with heating cables in both frame / threshold and door blade.

A) Technical Specification **HS 9020G**




HS9020G



SIDE GUIDES



Safety Facilities



Sr. No	Description	Specifications
1	Structure	Galvanized steel
2	Colours	8 standard colors - white, yellow, green, orange, red, gray, black, blue
3	Safety	• Photocells in side columns • Flexible soft bottom edge including wireless edge activator • Break-away and self-repair function
4	Operation	Operator + control unit
5	Operating speed	Opening: up to 1,2 m/s (optional 2,0 m/s) ; Closing: 0,5 m/s
6	Wind load resistance	Class 1 (300 Pa (N/m^2)) maximum wind load while closing 50 N/m^2
7	Air permeability	Class 1 (24 $m^3/m^2/h$ at 50 Pa)
8	Water penetration	Class 2 (50 Pa (N/m^2))
9	Thermal transmittance	6,02 $W/(m^2K)$
10	Lifetime expectations	1.000.000 cycles
11	Temperature working range	5 °C to +40 °C
12	Vision window	Horizontal one row of height 400 mm at eye level

C) **Technical Specification** **Sectional Door**

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Opening Direction**	Vertical Lift	
2	**Type of Mounting**	High Lift	
3	**Door produced Based on which certification**	Doors produced according to ISO 9000 or ISO 14000 certified processes	
4	**Opening/Closing Speed**	0.25 m/s	
5	**Door Material**	GI Steel with PUF inside	
6	**Panel Thickness**	42mm	
7	**Panel colour**	RAL 9002 Powder coated	
8	**External surface of the panel**	diamond grid design with a glossy finish at the section joints.	
9	**inside surface of the panel**	Monolithic surface on inside of the door	
10	**Broken cold bridge**	Section joints with broken cold bridges	
11	**Door sealent**	All door sealants made of EPDM rubber.	
12	**All Panel height**	All panels should be 545mm high	
13	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
14	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
15	**Steel component Material**	All steel components to be electro galvanized	
16	**Hinge Material**	Glass fibre reinforced Polyamide	
17	**Spring Material surface finish**	Powder coated	
18	**Water Penetration**	EN 12425	class 3
19	**Air Permealibity**	EN12426	class 2
20	**Wind Load**	EN21424	class 3
21	**Thermal Transittance**	EN 12428 1.10W /m2K	
22	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
23	**Door saftey device 1**	Doors equiped with spring break device	
24	**Door saftey device 2**	Door equiped with pneumatic safety edge	
25	**Door saftey 3**	Having hinges flush with the inside door surface is a safety feature that eliminates the risk of things or people getting caught by parts	
26	**Incase of Power failuer**	One can operate the Door manually	
27	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
28	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft	
29	**Emergency Operation**	by Disengagement rope manual	
30	**Operating Switch**	Up/Down Keypad + stopbutton	
31	**Environmental Green Product Declaration Certification**	as per ISO 14025 and EN 15804	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd