NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt Ltd
Samarth House, S.NO.116, Hissa No.3/1, 3/3,3/10,
Pune- Bangalore Highway, Near Shell petrol Pump,
Warje, Pune – 411058.

Date : 28.10.2020
Quote NO : SQT.20.21.2760
Kind Attn : Jitesh S. Darvatkar
Email Id : jiteshd@sconprojects.com
Contact No: 8928770959

Project Name & Location: Crane Process Flow Technology Pvt Ltd, Satara.

Subject : Quotation for Motorised Rolling Shutter, Boom Barrier, Sectional Door, High Speed Door and Sliding Gates.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	3500	3600	1	116,000	116,000	20,000	20,000
2	Motorized Rolling Shutter	3000	3200	2	101,000	202,000	20,000	40,000
3	Motorized Rolling Shutter	4000	3000	1	114,000	114,000	20,000	20,000
4	Motorized Rolling Shutter	3000	3000	5	98,000	490,000	20,000	100,000
5	Motorized Rolling Shutter with Grill	3000	3000	1	115,000	115,000	20,000	20,000
6	NIHVA MAKE Sectional Doors (Vertical Lift)	3000	3000	1	230,000	230,000	20,000	20,000
7	NIHVA MAKE Sectional Doors (Vertical Lift)	4000	3000	1	250,000	250,000	20,000	20,000
8	NIHVA MAKE High Speed Doors	3000	3000	1	250,000	250,000	20,000	20,000
9	NIHVA MAKE High Speed Doors	4000	3000	1	280,000	280,000	20,000	20,000
10	Automatic Sliding Gate	16000	1500	2	520,000	1,040,000	20,000	40,000
11	Automatic Sliding Gate	6000	1500	1	320,000	320,000	20,000	20,000
12	Wicket Gate	1200	1200	2	35,000	70,000	10,000	20,000
13	Wicket Gate	1000	1350	2	25,000	50,000	10,000	20,000
14	Boom Barrier		5000	3	129,000	387,000	15,000	45,000
15	Boom Barrier		4000	3	129,000	387,000	15,000	45,000
				Total		**4,301,000**		**470,000**
16	P&F Charges			3%		**129,030**		
	Total Without Taxes					**4,430,030**		**470,000**
	GST Extra @ 18%			18%		797,405		84,600
	Total With Taxes					**5,227,435**		**554,600**
17	Transportation Charges					**In Client Scope**		
18	Unloading Charges @ Site					**In Client Scope**		

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Motorized Rolling Shutter with Grill

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	On Concrete /Steel
4	**Curtain Panel**	The panel made of 1.0mm thick.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm
12	**Surface finish**	Powder Coating
13	**Honeycomb Grill**	600mm grill at 3000mm height from Bottom.
14	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA MAKE Sectional Doors (Vertical Lift)

Sr. No	Description	Specification
1	**Opening Direction & Mounting**	Standard (Vertical)
2	**Door Material**	Steel
3	**Panel Thickness**	42 mm Square Grid, steel sheet
4	**Filling**	CFC-free polyurethane
5	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant - 30/+70
6	**Water Penetration**	EN 12425 class 3
7	**Air Permealibity**	EN12426 class 3
8	**Thermal Transittance**	EN 12428 1.10W /m2K
9	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
10	**Door saftey**	Doors equiped with spring break device
11	**Incase of Power failuer**	Doors to be equiped with quick release fuction
12	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
13	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft
14	**Emergency Operation**	by Disengagement rope manual
15	**Operating Switch**	Up/Down Keypad + stopbutton
16	**Locks : Lock bolt**	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
17	**Environmental Green Product**	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA MAKE High Speed Doors

Sr. No	Description	Specifications
1	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
2	Opening speed	upto 3 m/s
3	Closing speed	0.8 m/s
4	Control Panel	4 Push Button operated
5	Security Features	EN 13241-1 Standard
6	Resistance to wind load	EN12424 upto class 1
7	Curtain	Fabric Transparent PVC section
8	Guide Material	Aluminum
9	Hood Cover	GI
10	Motor Cover	GI
11	Operator & Control	German Make Motor
12	Connecting Voltage	220V , 1Ph , N
13	Open-Stop-Close Button	Standarad
14	Protection Category	IP 54 / IP 65
15	Power Consumption	0.75 kw Motor
16	Emergency Off Button	Standard
17	Closing Zone Monitoring	Optical Safety edge
18	External Route Monitoring	Photocell
19	Emergency Opening	Crank Handle

Motorized Sliding Gate

Sr .No.	Specification	Motorized Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	100 X 50 X 3 mm THK SQ. TUBE
6	**For Post**	100 X 50 X 3 mm THK SQ. TUBE
7	**Inner Vertical Flat**	50 X 5 mm FLAT
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

Telescopic Sliding Gate

Sr .No.	Specification	Telescopic Sliding Gate
1	**Door type**	Motorised Three Leaf Telescopic Sliding Gate
2	**Clear Opening gate dimension**	(W) 16000 mm X (H) 1500 mm
3	**Opening Direction**	Horizontal - from left to right or reverse
4	**Mounting Location area**	Inside area
5	**Design Pattern**	Standard Tubular Design Pattern
6	**Outer Frame Tube Sizes**	100 X 50 X 3 mm THK SQ. TUBE
7	**Internal Vertical Tube Sizes**	FLAT 50 X 5
8	**For Post**	100 X 50 X 3 mm THK SQ. TUBE
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
13	**Motor**	100% Imported from Europe
14	**Operation**	By Telescopic Mechanism

Boom Barrier

Sr .No.	Description	Specifications
1	**Size**	4 meter / 5 meter
2	**Opening time**	3S
3	**Motor Power Supply**	24V
4	**Type of limit Switch**	Electronic
5	**Safety**	Photocell sensor, Flashing Light With Buzzer
6	**Operated**	Push Button Pedant

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd