NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Tata Cummins Pvt. Ltd
Phaltan

Date : 15.02.2020
Quote NO : SQT.19.20.2441
Kind Attn : Mr. Debashis Pattanaik
Email Id : debashis.pattanaik@cummins.com
Contact No : 7722028263

Project Name & Location: TATA Cummins Phaltan

Subject : Quotation for Rolling Shutter, Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Option 1 :** **GI Motorised Rolling Shutter**	4000	5000	7	1,32,000	9,24,000	15,000	1,05,000
2	**Option 2 :** **Automatic Sectional Door**	4000	5000	7	3,07,000	21,49,000	15,000	1,05,000
3	**Removing of Existing Sectional Door**	4000	5000	7			15,000	1,05,000
				Total				
4	P&F Charges			3%		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
5	Transportation Charges					**Extra at Actual**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1.Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	Powder Coated
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Sprocket chain arrangement

2. Sectional Door

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Door type**	1042P	
2	**Door produced Based on which certificatio**	Doors produced according to ISO 9000 or ISO 14000	
3	**Opening/Closing Speed**	0.25 m/s	
4	**Door Material**	GI Steel with PUF inside	
5	**Panel Thickness**	42mm	
6	**Panel colour**	RAL 9002 Powder coated	
7	**External surface of the panel**	diamond grid design with a glossy finish at the section	
8	**inside surface of the panel**	Monolithic surface on the inside of the door	
9	**Broken cold bridge**	Section joints with broken cold bridges	
10	**Door sealent**	All door sealants made of EPDM rubber.	
11	**All Panel height**	All panels should be 545mm high	
12	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
13	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
14	**Steel component Material**	All steel components to be electro galvanized	
15	**Hinge Material**	Glass fibre reinforced Polyamide	
16	**Panel Thickness**	42 mm	
17	**Spring Material surface finish**	Powder coated	
18	**Water Penetration**	EN 12425	class 3
19	**Air Permealibity**	EN12426	class 2
20	**Wind Load**	EN21424	class 3
21	**Thermal Transittance**	EN 12428 1.10W /m2K	
22	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
25	**Door saftey device**	Door equiped with pneumatic safety edge	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil structural work required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 5-6 Weeks for Rolling shutter and 10 -11 weeks for Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333 .**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd