NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

NeoSilica Technologies Pvt Ltd
7Q2A3, Cyber Towers, Hitech City, Hyderabad
TS 500081, INDIA

Date : 24.09.2020
Quote NO : SQT/20-21/2712R
Kind Attn : Mr. Veerababu T
Email Id : veera@neosilica.com
Contact No: 91000 28956

Project : Konkan Railways, Chipalun, Maharashtra

Subject : Quotation for Sliding Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**MOTORISED SINGLE LEAF SLIDING GATE**	7500	2200	6	4,36,000	26,16,000	20,000	1,20,000
2	**MOTORISED SINGLE LEAF SLIDING GATE**	9500	2200	1	4,94,000	4,94,000	20,000	20,000
3	**MANUAL WICKET GATE**	1850	2200	7	40,000	2,80,000	5,000	35,000
4	**Boom Barrier**	6000		7	1,25,000	8,75,000	20,000	1,40,000
5	**Boom Barrier**	8000		1	1,65,000	1,65,000	20,000	20,000
				Total		**44,30,000**		**3,35,000**
5	P&F Charges			0%		-		
	Total Without Taxes					44,30,000		3,35,000
	GST Extra @ 18%			18%		7,97,400.00		60,300
	Total With Taxes					**52,27,400**		**3,95,300**
6	Transportation Charges					Included		
7	Unloading Charges @ Site					In Client Scope		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **TECHNICAL SPECIFICATION - SLIDING GATE**

NIHVA make – Motorized Single Leaf Sliding Gate		
Sr. No.	**Door type**	**Motorized Sliding Gate**
1	**Opening Direction**	**Horizontal - from left to right or reverse**
2	**Mounting Location area**	Inside area
3	**Design Pattern**	Standard Tubular Design Pattern
4	**Outer Frame Tube Sizes**	100 x 100 x 3.6 mm THK SQ. TUBE
5	**Internal Vertical Tube Sizes**	38 x 38 x 2.6 mm THK SQ. TUBE
6	**Post Tube**	100 x 100 x 3.6 mm THK SQ. TUBE
7	**Gap Between Tubes**	125 MM
8	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
11	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
12	**El motor make**	BFT – Italy (100% imported)
13	**Operating Switch**	Push Button from inside
14	**Safety**	Photocells, Flashing Light
15	**Metal Rack**	zinc plated metal rack

Technical Specs - Boom Barrier

Sr. No.	Description	Specifications
1	Size	6 Mtr
2	Model No	Michealangelo 60
3	MICHELANGELO BT A Barrier	Opening Time- 6S
4	Motor Power Supply	24V
5	Type of limit Switch	Electronic
6	Safety	Photocell sensor
7	Operated	Push Button Pedant

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Chipalun

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551096333
For NIHVA Technologies Pvt Ltd