NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Prism Johnson Limited
Mankahari, Satna, Pin-485111

Date : **29.11.2019**
Quote NO : **SQT.19.20.2277**
Kind Attn : **Mr. Neerav Saxena**
Email Id : neerav.saxena@prismjohnson.in
Contact No: **9584460874**

Subject : Quotation for High Speed Door RR 392

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
Option 1								
1	**Albany Make Rapid Roll Up Door RR 392**	4320	4800	1	8,17,000	8,17,000	20,000	20,000
Option 2								
2	**Albany Make Rapid Roll Up Door RR 300 Plus Alu**	4320	4800	1	6,79,000	6,79,000	20,000	20,000
3	P&F Charges				**3% Extra On Total**			
	GST Extra @ 18%				**18% extra on Total with P&F**		**18% extra on Total**	
4	Transportation Charges				**In Client Scope**			
5	Unloading Charges @ Site				**In Client Scope**			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Rapid Roll Up Door RR 392

Sr. No.	Description	Specification
1	Door type	RR392 (External Application)
2	Description	Flexible High Performance Door, opening in vertical direction, for interior and exterior use
3	Side frames	Bended galvanized steel profiles. All steel parts galvanized, springs for curtain tension and counterbalance in the side frame
4	Door curtain	Transparent PVC with vertically applied side reinforcement stripes, ultramarine (similar to RAL 1021)
5	Wind protection	Through wind taps on the door curtain
6	Wind resistance	Class 2 (EN 12424)
7	Bottom profile	Anodized aluminum
8	Drive unit	Gear motor
9	Protection	IP 55
10	Control system	MCC Vector Control, based on vector control system including boost function for start-up
11	Supply voltage	Supply voltage 3L(N)PE/380/400/415/440/480V;50/60Hz, Transformer necessary for 220/230/500V; 50/60 Hz
12	Safety devices	Electrical safety contact edge, stationary safety photocell, and drop down protection by integrated balancing system.
13	Manual activation	By releasing the brake at ground level.
14	Opening Closing Speed	(Open/close) up to max. 2.2/0.9 m/s,

RR 300 Plus Alu

Sr. No.	Description	Specification
1	Door type	RR300 Plus
2	Description	Flexible High Performance Door, opening in vertical direction for interior use in wind-protected areas
3	Side frames	Made of aluminum
4	Door curtain	(similar to RAL 1021) (similar to RAL 3002).
5	Top roll	Made of anodized aluminum
6	Wind protection	wind tabs on the door curtain
7	Wind resistance	Class 1 (EN 12424).
8	Bottom profile	anodized aluminum
9	Drive unit	Hollow shaft gear motor
10	Protection	IP 55
11	Control system	Frequency converter control system MCC Vector Control, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service,
12	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz Transformer necessary for 220/230/500V
13	Safety devices	electrical safety contact edge, evaluation via integrated cable chain, door line photocell in the side frames, drop down protection by integrated balancing system
14	Manual activation	By releasing the brake at ground level. Depending on width/height ratio the door opens up to max. 2.0 m
15	Opening / closing Speed	(open/close) up to max. 2,2/0,9 m/s,

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8530370333
For NIHVA Technologies Pvt Ltd