NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/1295B **Date : 01-07-2019**

Ratnarup Projects Pvt. Ltd.,
Baner
Pune

Kind Attn: Mr. Ajit Jadhav
Email: ajit@ratnarupprojects.com
Contact: 9623589393

Project Name And Location : Stihl, Chakan, M.I.D.C., Phase-3 site.

Subject : Quotation for MS Fire rated Rolling Shutter.

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty.	Unit	Rate In INR	Net Amount INR
A	**2 Hrs Fire Rated Rolling Shutter** **Made in India with BS476 certification** **Shutter Slats: Zinc coated steel solid slats** **• Slat Thickness: 1.0 mm thick** **• Shutter Guide: Galvanize Steel of 3 mm thick** **• Operated by: Motorize with one unit push button switch & manual override** **• Opening/Closing Speed : 0.2 m/s** **• Radar Sensor for automatic opening of Door** **(Supply + Installation)**				
1	**Size : (W) 2500 mm x (L) 4000 mm**	1	No	309,000	309,000
B	**<u>Gear Operated Rolling Shutter</u>** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover : 1.2 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation)**				
1	**Size :** (W) 2500 mm x (H) 4000 mm	1	No	90,000	90,000

GST Pune:	27AAECN0437H1ZM

Total	**309,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry / structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provide structure drawing only if required
5. Existing / Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3 % of total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	8 -9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @ 18% Extra
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr.Swapnil Kulat** on **7219207333** For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti

7219206333

For NIHVA Technologies Pvt Ltd