NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SCON Projects Pvt. Ltd
Samarth House,
S.NO.116, Hissa No.3/1, 3/3,3/10,
Pune - Bangalore Highway,
Near Shell petrol Pump, Warje, Pune – 411058.

Date : 25.09.2020
Quote NO : SQT.20.21.2723
Kind Attn : Bishnu Prasad Naik
Email Id : bishnuprasadn@sconprojects.com
Contact No: 9657722408

Subject : Quotation for Motorized Rolling Shutter and Dock Leveler. (Project Location - Kerakoll India Pvt Ltd, GUJARAT).

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	5000	4000	3	160,000	480,000	20,000	60,000
2	Motorized Rolling Shutter	3000	3000	1	105,000	105,000	20,000	20,000
3	NIHVA Dock Leveller - Capacity 15 Ton	2000 (W)	3500 (L)	3	250,000	750,000	20,000	60,000
				Total		**1,335,000**		**140,000**
4	P&F Charges			3%		40,050		
	Total Without Taxes					1,375,050		140,000
	GST Extra @ 18%			18%		247,509.00		25,200
	Total With Taxes					**1,622,559**		**165,200**
5	Transportation Charges					Extra at Actual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **TECHNICAL SPECIFICATION -**

Motorized Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved with Grill of 5 sqm at center
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	Painting - Powder coating
13	**Drive Unit & Mounting Type**	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

Dock Leveller

Sr. No	Description	Specifications For 15 Ton
1	Make	NIHVA
2	Required Capacity	15 Ton
3	Hydraulic Power pack	1 HP, 3PH
4	Control Panel	4 Push Button operated
5	Deck operation	By push button Deck UP & Deck Down
6	Lip operation	By push button Deck UP & Deck Down
7	Loading platform height from road Level	4 feet (1250 mm)
8	Travel above & below dock level	(+) 350 / (-) 200 mm
9	Deck platform size	2000mm (W) x 3500mm (L)
10	Lip sizes	410 mm
11	Clear Pit dimensions	2040mm (W) x 3500mm (L) x 550 mm (H)
12	Drive type	Direct by electric Motor
13	Power Consumption	0.75 kw Motor
14	Degree of protection for motor	IP 55
15	Motor RPM	1410 rpm
16	Pump design flow	1.8 LPM
17	Pump pressure	200bar
18	Safety valve set pressure	110 bar
19	Pump type	Gear
20	In built safety valve	Yes
21	Volume of oil receiver	8 Ltr
22	No of Deck Cylinders	2 Nos
23	Deck Plate Thickness	8 mm Chequered Plate
24	No of Lip Cylinders	1 No
25	Lip Plate	16 mm Thick Plate
26	Dock Bumpers	1 Pair included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks for Dock Leveler & Rolling Shutter from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd