NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Gruha IBC Pvt. Ltd
Yandnya, Plot no.4 , nr Ovi building, & lateral side of Bhintade builders
S.No55/3A, Vadgaon bk , Sinhgad road Nr.Nawale Bridge, Next to Ovi Apartment
Pune-411041. Maharashtra , India

Date : 04.06.2020
Quote NO : SQT/19-20/2551
Kind Attn : Mr. Bhalchandra Kulkarni
Email Id : bhalchandra.kulkarni@gruhaibc.com
Contact No: 9860501755

Subject : Quotation for Fire rated Rolling Shutter and High Speed door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**2 Hrs Fire Rated Rolling Shutter**	4000	4500	3	3,78,000	11,34,000	20,000	60,000
2	**High Speed Door**	4000	4500	3	5,28,000	15,84,000	20,000	60,000
				Total		**27,18,000**		**1,20,000**
3			P&F Charges	3%		81,540		
			Total Without Taxes			27,99,540		1,20,000
			GST Extra @ 18%	18%		5,03,917.20		21,600
			Total With Taxes			**33,03,457**		**1,41,600**
4			Transportation Charges			Extra at actual		
5			Unloading Charges @ Site			In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	SKB - BS476
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Model : SKB-G65 powder coated
3	**Bottom Bar**	Model : SKB-T120 powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal

High Speed Door RR300+ Al

Sr. No	Description	Details
1	Size	(W) 4000 mm X (H) 4500 mm
2	Quantity	3 Number
3	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
4	Barrel:	Aluminium, anodized with shafts made of galvanized steel
5	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
6	Side Frames:	Aluminium profiles, anodised
7	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
8	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
9	Bottom beam:	Anodized extruded aluminium.
10	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
11	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd