Customer: NIVHA Technologies Date: 2/12/21

Quotation Code: HE-P-1/A

<table>
<tr><th>S.NO</th><th>Parameters</th><th>Description</th><th>Remark</th></tr>
<tr><td></td><td></td><td></td><td></td></tr>
<tr><td>1</td><td>Application</td><td>Palletizer</td><td></td></tr>
<tr><td>2</td><td>Packing system & Its Basic Features</td><td>Basic design Features.
1. Structure will be powder coated/ Chrome plating
2. Design of structure is modular which can be dismantled and assembled.
3. Pneumatic cylinders, motors & sensors are used for automation.

Design Components:

<table>
<tr><td>S.no</td><td>Component</td><td>Application</td></tr>
<tr><td>1.</td><td>Box transfer unit</td><td>Grid formation is placed on this unit from where it transfers to pallet.</td></tr>
<tr><td>2.</td><td>Lift conveyor</td><td>For placing Box grid one above the other</td></tr>
<tr><td>3.</td><td>Box transfer roller conveyor</td><td>Single boxes forms grid on this conveyor.</td></tr>
<tr><td>4.</td><td>Box Pusher Unit</td><td>Formed Box Grid on roller conveyor is transferred via this pusher unit</td></tr>
<tr><td>5..</td><td>Pallet Transfer chain conveyor</td><td>To Transfer pallets to appropriate location.</td></tr>
<tr><td>6.</td><td>Pallet Dispenser</td><td>Stack of 5 pallet is collected on this conveyor and released one by one.</td></tr>
<tr><td>7.</td><td>Control Panel</td><td>All Automation is controlled from control panel</td></tr>
</table>
</td><td></td></tr>
<tr><td>6</td><td>Control Panel & Its Basic Features</td><td>Cabinet:
1. Main control panel : Floor mounted cabinet
Approx. size: 1200(L) X 500(W) X 1500(H)

Switch Gear:
1. Main Isolation through MCCB.
2. Interlocks through main contractor
Junction box:
Cabinet cooling : Fans are provided for cabinet cooling</td><td></td></tr>
</table>

Heat-EN Infrared Heating Systems Pvt Ltd
Gate no: 155,opp Ashok Leyland
Chimbli Phata, Kuruli, Talkhed, Pune,
Maharashtra 410501
sales@heaten.in
Ph: 8983410515
8983410515
GST NO: 09AAFCH6107H1ZM

<table>
<tr><td></td><td>PLC & Automation</td><td>1. Siemens PLC is used for automation control.
2. 5” HMI for Control input & alarm display</td><td></td></tr>
<tr><td></td><td>Components & Make list.</td><td>Only reputed bought-out components are used. The price is worked out on the basis of make list provided. Any other makes other than this should be mentioned prior to order so than final price & delivery schedule can be concluded.

<table><tr><th>Components</th><th>Make</th></tr><tr><td>Control Panel Cabinet</td><td></td></tr><tr><td>MCB</td><td>Siemens</td></tr><tr><td>Indicator Lamps, selector switch & push buttons</td><td>Technik</td></tr><tr><td>Wires inside control Panel</td><td>Finolex / Polycab</td></tr><tr><td>Terminals in control panel</td><td>Connectwel/ Wago</td></tr><tr><td>PLC</td><td>Siemens</td></tr><tr><td>HMI</td><td>5” HMI, Siemens</td></tr><tr><td>Isolation Transformer</td><td>NANAP/AE</td></tr><tr><td>Relay</td><td>Omron/ Phoenix</td></tr><tr><td>Cooling Fans</td><td>Sunon</td></tr><tr><td>VFD</td><td>Siemens</td></tr><tr><td>Pneumatics</td><td>janatics</td></tr><tr><td>Power Supply</td><td>Omron</td></tr></table></td><td></td></tr>
<tr><td></td><td>Cables & its Scope of supply</td><td>Customer’s scope:
1. All Cables from control panel to terminal box will be in Customers scope.
Supplier’s Scope:
2. Cables from terminal box to system maximum up to 4mts will be provided.
Cable schedule will be provided after order finalization.</td><td></td></tr>
<tr><td>7</td><td>Final Testing</td><td>Final Pre dispatch inspection will be offered. this will be done on the basis of Validation sheet mutually agreed at the time of GA approval</td><td></td></tr>
<tr><td>8</td><td>Delivery schedule</td><td>The delivery schedule begins after the receipt of order.
Delivery will be 6-8 weeks.</td><td></td></tr>
<tr><td>9</td><td>Documentation</td><td>1. All G.A. Drawings & validation sheet will be provided.
2. Electrical diagrams and mechanical diagrams will be as per DIN standards.
3. Two sets of hard copy of operating manual will be provided at the time of dispatch.</td><td></td></tr>
</table>

10	**Packing & Transportation**	customer scope	
11	**Installation and Commissioning & Training**	**Separate quotation will be provided.** Our commissioning Engineer will explain entire control panel functionalities and the manual. This may take about 1-2 days	
12	**Warranty**	The equipment is guaranteed against any manufacturing defects for a period of 12 months from the date of control panel commissioning or 16 months from the date of delivery.	
13	**Exclusion from warranty**	1. The warranty does not cover normal wear and tear. 2. Defects arising out of breakage and mishandling are excluded from this warranty.	
14	**Post warranty Service**	We recommend our AMC (Annual Maintenance Contract) service after warranty period.	
15.	**Payment Terms**	1. 60% Advance 2. Balance before dispatch	
	Total Amount for the Design, Manufacturing, Assembly &Testing.		**19,25,000 + 18% GST**
		Nineteen Lakh twenty five thousand only	
This Quotation is valid for 6 month only.			