NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SEZ Biotech Services Pvt Ltd
Manjari Bk., Tal. Haveli, Pune 412207 (India)

Date : 09.08.2021
Quote NO : SQT.20.21.2773R12
Kind Attn : Nilesh Patil
Email Id : nileshpatil.purchase@seruminstitute.com
Contact No: 8451842931

Subject : Revised Quotation for Teckentrup make Double Skin Motorised Rolling Shutter (High Sea Sale)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer -Price is High Sea Sale (Custom Duty + Custom Clearance + Local Transport will be in Serum Scope)

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Teckentrup make Double Skin Motorised Rolling Shutter - Including Structure - Made in Germany**	4515	8200	10	616,000	6,160,000	15,000	150,000
	Total			**10**		**6,160,000**		**150,000**
	P&F Charges			0%		-		
	Total Without Taxes					**6,160,000**		**150,000**
	GST Extra @ 18%			NIL	Due to SEZ			
	Transportation Charges					**Inclusive**		
	Unloading Charges @ Site					**Inclusive**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Double Skinned Teckentrup Rolling Shutter with MS Structure

Sr .No.	Specification	Double Skinned Teckentrup Rolling Shutter with MS Structure
1	Door Curtain	ThermoTeck steel filled with PU-foam
2	Roller door surface outside	Galvanised with protective fill
3	Door Colour Inside/ Outside	Uniformly (Bare Galvanised)
4	Buffer Drive side min/exist.	325 mm / 325 mm
5	Buffer bear side min./exist.	200 mm / 200 mm
6	Lintel height min./ exist.	700 mm / 700 mm
7	Insertion Depth	948 mm
8	Building Structure	Concrete
9	Bottom Profile	ET-1 for Teckentrup ThermoTeck
10	Welding Shaft	Steel Tube 159 mm primed
11	Guide rail	FS 110 steel
12	Underlining Size	60 mm
13	Console Drive/ Bearing Side	Console Type 7.5
14	Brush sealing Type	BH - 50
15	Drive Type	Direct Mount Drive TAR 5.75 KU 400 V/3Ph AWG 12 U/min; IP54; 60% ED
16	Drive mounted	Inside Left, standing
17	Emergency Drive Operation	emergency hand crank
18	Door operation control unit	Normal operation quantity CS310 (Pulse) with built in triple button CEE plug with wire
19	Safety edge device:	opto-sensors
20	Control Cable length	9.000 mm
21	Wind resistance:	Wind load resistance class 3
22	Heat transmis value (W/m2K)	3,34
23	Structure for fixing Rolling Shutter 4515 mm X 8200 mm	
24	**HSN CODE**	**73080000**

Teckentrup sectional doors/ roller doors

For roller doors and sectional doors with more than 70 cycles a day or more than 20 cycles per hour we recommend using a motor with 100% rating.

For doors with more than 10,000 cycles a year we recommend the use of reinforced torsion springs (increased load cycle).

The lintel seal of sectional doors with low headroom (NSH/NSD) and a lintel of only 250mm may catch on the ceiling and may leave scuff marks.

Teckentrup aluminium roller door 4020

The smooth version of the roller door 4020 can develop abrasive marks -this is due to technical reasons and will not entitle to warranty or replacement- therefore we recommend the stucco embossed material which conceales any abrasive marks.

Doors with powder coated surfaces can have increased running noises.

Galvanised surface with transparent protective paint

This is manufactured cold formed galvanised sheet, there is no paint coating.

Consider possible environmental influences (such as sea climate, aggressive vapours in the atmosphere, road salt, exposure to abrasive materials, increased wind loads). Where appropriate subsequent protective paints may be required.

To ensure there is sufficient water run-off in front of the door and on the frame parts a minimum fall away of 2-3° is suggested to prevent water standing and puddling (risk of corrosion)

We reserve the right to amend charges if measurements and technical specifications change.,

Inspection and maintenance instructions

For power operated doors in a factory or public place the Machinery at Work Act denotes that a maintenance schedule must be in place with yearly safety inspections.

We recommend that Teckentrup industrial doors with more than 50 cycles a day be inspected every 6 months, and doors with more than 100 cycles a day be tested every 3 months.

Non-compliance with the above mentioned tests can cause risk of injuries and danger of property damage and will invalidate warranty rights.

Environmental product declaration:

"Teckentrup Türen und Tore" are declared by the ift Rosenheim - EPD (environmental product declaration)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.
2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4 Price is High Sea Sale (Custom Duty + Custom Clearance + Local Transport will be in Serum Scope)
5 Insurance from MUMBAI Port till Site will be in NIHVA Scope.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remarks
1	Secured and fully covered Store area to keep the material	Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	Client Scope
4	Any civil / masonry/structural work required	Client Scope
5	All structure support required	NIHVA Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	Client Scope
7	Conduits, Cables required	Client Scope

D) Terms & Conditions

Price : CIF Mumbai

Delivery : 10 - 12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 25% Advance along with Confirmed Purchase Order against ABG, 75% against submission of bill of lading.

Validity : Validity of Offer is 3 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Vijay Tarak on 8551093333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd