NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Flexli Technologies
Bangaluru

Date : 25.09.2019
Quote NO : SQT.19.20.2114
Kind Attn : Mr. Sanjeev
Email Id : sanjeev@flexli.in
Contact No: 7888047277

Project Name & Location: Telescopic Conveyor; Bangaluru

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description
A.	Commercial Offer
B.	Technical Specification
C.	General Conditions
D.	Terms & Condtions

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Total length of conveyor (mm)	Width Of Conveyor (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Telescopic Conveyor	12000	1000	1	9,28,290	9,28,290	50,000	50,000
				Total		**9,28,290**		**50,000**
2			P&F Charges	3%		**27,848.70**		
			Total Without Taxes			**9,56,139**		**50,000**
			GST Extra @ 18%	18%		1,67,092.20		9,000
			Total With Taxes			**11,23,231**		**59,000**
3			Transportation Charges			**In Client Scope**		
4			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

1 Technical Specification- Telescopic Conveyor

Description	Specification
Total length of conveyor	12000 mm
Collapsed length	5000 mm
Telescopic Length	7000 mm
Width Of Conveyor	1000 mm
Width Of Conveyor Belt	600 mm
Conveyor Capacity	35 kg / mtr
Speed	30 mtr / min (Variable speed)
Drive Type :	
Conveying	Auto/ Manual
Telescopic	Auto/ Manual
Hydraillic Lifting Support	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8- 10weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Swapnil Kulat on 7219207333**

With Best Regards
Yogita
8208334981
For NIHVA Technologies Pvt Ltd