**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Address**
20, Chinar park, Rajarhat,
Gopalpur, Kolkata-700157

**Date : 27.11.2019**
Quote NO : SQT.19.20.2280
**Kind Attn : Mr. Chittaranjan Das**
Email Id : chittaranjan.das@kutchina.com
Contact No: 8285517056

**Project Name & Location: Telescopic Conveyor and Dock Leveller**

**Subject : Quotation for Telescopic Conveyor and Dock Leveller**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply and Installation Charges in INR | |
|---|---|---|---|---|---|---|
| | | Total length of conveyor (mm) | Width Of Conveyor (mm) | (Nos) | Unit Price | Total Amount |
| 1 | Telescopic Conveyor | 12500 | 1500 | 1 | 6,51,000 | 6,51,000 |
| | | | | **Total** | | **6,51,000** |
| | | | | P&F Charges | **3%** | **19,530** |
| | | | | **Total Without Taxes** | | **6,70,530** |
| | | | | GST Extra @ 18% | 18% | 1,20,695.40 |
| | | | | **Total With Taxes** | | **7,91,225** |
| 2 | | | | Transportation Charges | | **In Client Scope** |
| 3 | | | | Unloading Charges @ Site | | **In Client Scope** |

| Sr No | Description | Size | | Qty | Supply and Installation Charges in INR | |
|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount |
| 2 | Nihva Make Dock Leveller (Capacity - 10 Ton) | 2030 | 2700 | 1 | 2,50,000 | 2,50,000 |
| | | | | **Total** | | **2,50,000** |
| | | | | P&F Charges | **3%** | **7,500** |
| | | | | **Total Without Taxes** | | **2,57,500** |
| | | | | GST Extra @ 18% | 18% | 46,350.00 |
| | | | | **Total With Taxes** | | **3,03,850** |
| 2 | | | | Transportation Charges | | **In Client Scope** |
| 3 | | | | Unloading Charges @ Site | | **In Client Scope** |

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

**B) Technical Specification**

| Description | Specification |
|---|---|
| Total length of conveyor : | 12500 mm |
| Collapsed length: | 4500 mm |
| Telescopic Length: | 8000 mm |
| Width Of Conveyor : | 1500 mm |
| Conveyor Capacity: | 50 kg / mtr |
| Speed: | 5 mtr / min ( Variable speed) |
| Drive Type : | |
| Conveying : | Auto/ Manual |
| Telescopic: | Auto/ Manual |

| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Capacity | 10 Ton |
| 2 | Dock operation mode | AC power pack hydraulically operated |
| 3 | Lip operation mode | Hydraulic |
| 4 | Operation control | Through panel |
| 5 | Loading platform height from road | 1250mm |
| 6 | Travel above & below dock level | (+) 300 / (-) 250 mm |
| 7 | Platform Size (W x L) | 2030 mm x 2720 mm |
| 8 | Lip size (W x L ) | 2000 x 400 mm |
| 9 | Shut Height | 485 mm |
| 10 | Working length | 3120 mm |
| 11 | Maximum slope can be achieved | 0.1 |
| 12 | Clear Pit dimensions (W x L x D) | (W) 2080mm x (L) 2770 mm x (D) 485 mm |
| 13 | Hydraulic power pack | Standard |
| 14 | Driver type | Direct by electric Motor |
| 15 | Motor Ratings | 1 H.P Crompton Greaves Make |
| 16 | Pump design flow | 2.5 LPM |
| 17 | Pump pressure | 120 bar Operating 200 bar Max. |
| 18 | Safety valve set pressure | 120 Kg/cm² |
| 19 | Pump Type | Gear |
| 20 | Volume of oil receiver | 7 Lit |
| 21 | No Of Deck cylinder | 2 No |
| 22 | Lip Cylinder | 1 No |
| 23 | Dock Bumper | Included |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1. Installation will start after receiving of Site Readiness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipments are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | | **Remark** |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8- 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply

With Best Regards
Pradip
7709586333
For NIHVA Technologies Pvt Ltd