NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Su-mech Storage Systems Pvt. Ltd
Pune

Date : 23.03.2021
Quote NO : SQT.20.21.3119
Kind Attn : Devendra Pawar
Email Id : sales@su-mech.com
Contact No: 8605682727

Subject : Quotation for Cantilever Sliding Gate.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Cantilever Sliding Gate	6000	2820	1	557,000	557,000	20,000	20,000
2	Cantilever Sliding Gate	6000	2640	2	552,000	1,104,000	20,000	40,000
				Total		**1,661,000**		**60,000**
3	P&F Charges			3%		49,830		
	Total Without Taxes					1,710,830		60,000
	GST Extra @ 18%			18%		307,949.40		10,800
	Total With Taxes					**2,018,779**		**70,800**
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA make – Cantilever Gate

Sr. No	Specification	Motorised Single Leaf Cantilever Gate
1	**Door type**	Motorised Single Leaf Cantilever Gate
2	**Clear Opening gate dimension**	6000 mm X 2820 mm & 6000 mm X 2640 mm
3	**Master Leaf Size**	9560 mm X 2820 mm
4	**Opening Direction**	Horizontal - from left to right or reverse
5	**Outer Tube**	72 X 72 X 3.2 MM THK SQ. TUBE
6	**Inner Tube**	25 X 25 X 2.6 MM THK SQ. TUBE
7	**Gap Between Tubes**	125mm
8	**Post Tube**	72x72x3.2 MM
9	**Design Pattern**	Standard Tubular Design Pattern
10	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
11	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Operation**	By Cantilever Mechanism
13	**Operating Switch**	Push Button from inside
14	**Safety**	Photocells, Flashing Light , Safety Edge
15	**Civil work**	Client scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd