RMK Infrastructure Pvt. Ltd.

Work Order- JIS/AW/2021/007

Name of Company	RMK Infrastructure Pvt. Ltd.	**Contractor Name**	NIHVA Technologies Pvt. Ltd.
Address	Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507	**Address**	Jadhavwadi Industrial Shed Gate No-45, Talegaon,Pune,402111
		Contact Person	Mr. Arjun Patil
Project Name	Metjoy Jadhavwadi Gut No 45	**Contact No**	8551096333
		Email ID	support@nihva.com
Sub Project	GAT NO 45	**Work Order Type**	Labour With Material
Project Manager	Najir Shikandar Shaikh	**Work Order Date**	04/01/2021
Contact Number		**Service Requisition No.**	CR2021083
Project Email ID		**Service Requisition dt**	04/01/2021
Project Address	Jadhavwadi Industrial Shed Gate No-45		
Company Pan No	AAFCR0774G	**Vendor Pan No**	AAECN0437H
Company GST No	27AAFCR0774G1ZB	**Vendor GST No**	27AAECN0437H1ZM

Subject :	**Work order for Installation of Motorized Rolling Shutter and Boom Barrier with Mobile support at Jadhavwadi Gat No-45, Talegaon MIDC, Pune.**

Work Order Details

Sr No.	Particular	Unit	Qty	Rate	GST Rate	Gross Amt
1	Motorized Rolling Shutter- Design, Supply & Installation- 3000mm wide x 4000 mm tall -- Installation of Single Skin G I Motorized Rolling Shutter -Motorized rolling shutter Clear opening 3000mm wide x 4000 mm tall (Color RAL Code- 9007) from both sides as per Technical details (As per approved design) mention in work order ' OR ' as per instruction of site In-charge.	NOS	6.00	10,000.00	18	60,000.00
2	Motorized Rolling Shutter- Design, Supply & Installation- 6000mm wide x 5700 mm tall -- Installation of Single Skin G I Motorized Rolling Shutter -Motorized rolling shutter Clear opening 6000mm wide x 5700 mm tall (Color RAL Code- 9007) from both sides as per Technical details (As per approved design) mention in work order ' OR ' as per instruction of site In-charge	NOS	2.00	10,000.00	18	20,000.00
3	Boom Barrier- Design, Supply & Installation- Boom Barrier: - 4.4 m Length with mobile Support -- Installation of BOOM BARIEER - 4400 Mtr with Mobile Support as per Technical details (As per approved design) mention in work order ' OR ' as per instruction of site In-charge	NOS	2.00	10,000.00	18	20,000.00
					Total	**1,00,000.00**
					Input CGST	**9,000.00**
					Input SGST	**9,000.00**
					GST Total	**18,000.00**
					Grand Total	**118000.00**

Amount in word : One Lac Eighteen Thousand Only.

Terms and Condition:

Contact Person:- Mr. Najir Sikh- 8888842504, Mr. T D Patle- 8087745136

A) Safety & environment requirements: -

1 All the Operators/labors should be age of above 18 and below 55 years, no child labor shall be permitted at work site.

2 You will have to follow all Safety Measures at work site, and all PPE's for your workers is in your scope of work.

3 The equipment used by you must be in good working condition at all times.

4 All the equipment & operator needing RTO, registration will be duly registered with RTO, without any cost to us.

5 You will be responsible for all the accidents, mishaps occurring on your work site due to your equipment and you will attend to all legal matters/police matters in that respect without any cost to us.

6 Do not cut off any trees/plants without prior written permission by "RMK INFRASTRUCTURE PVT.LTD".

7 All Required safety PPE's & Equipment will be in NIHVA Technologies Pvt. Ltd. scope.

B) Statutory requirements: -

1 Electricity will be provided at one point by company, further any arrangements for works is in your scope of work.

2 You will have to meet all the statutory requirements of Government in respect of labor laws. You shall also submit one copy of such documents i.e. labor License, Workmen Compensation Insurance Policy/ESI, Migrant Certificate, Provident Fund, Professional Tax etc. as per your scope of work.

3 You have to maintain the attendance record; wages register of your labors and submit the same to us every month.

4 You will bear all the insurance charges for your manpower and equipment.

5 Arrangement & cost of Accommodation, fooding to your workers is your responsibility.

6 Contact person of "RMK INFRASTRUCTURE PVT.LTD." for all of your matters will be discussing to authorize persons (Related to bill- Billing department head, related to accounts- accounts head, and related to technical - site head).

7 For all matters related to this work order, legal jurisdiction will be PUNE.

C) Commercial Terms: -

1 For executing the work entrusted to you, we will not provide any equipment which is deemed to be deployed by you for the item of work. In case you need any equipment either owned by us or hired by us, we may make the same available to you if possible, the hire charges were will be debited to your account for period of use.

2 All accessories, spare parts, tires etc. as may be required for normal operation and for maintenance / repairs of the Machinery shall be provided by you at your cost and no extra charges shall be payable to you on this account.

3 This contract will be valid for an initial period of 1 Years from the date of this work order, which we may extend for a further suitable period depending on our requirements, for which we will give you at least 30 days advance notice. In case you will not be interested in such an extension of this contract, you shall give us minimum 30 days advance notice to enable us to make alternate arrangements.

4 We reserve our right to discontinue your services with prior notice of 24 hours.

5 You will not be paid any idling charges for your equipment or labor for any reason. You will be paid only for the quantity of work done as per the rates given in annexure to this work order.

6 In case of any dispute, the same will be referred to the Project Manager, "RMK INFRASTRUCTURE PVT.LTD.".-In charge of this project-whose decision shall be final and binding.

D) Payment condition: -

1 The rates of works entrusted to you and to be carried out by you will be as per schedule of rates in annexure.

2 Bill Submission Date- One time bill will be submitted by date 1st to 3rd day of month.

3 Your Payment will be made after one month from the date of bill submission with M.B. on actual measurement basis duly certified by our site engineer & billing department head.

4 The payment terms & other conditions are as follows.

i) 100% After commissioning certificate from RMKIPL's site in-charge for Rolling shutter & Boom Barrier and on submission of A) Original BG valid for 12 Months from commissioning certificate, amount will be same as equal to 10% amount of total contract's basic amount including Supply and Installation B) Warranty/Guaranty certificate for the Validity of 36 Months from Handing over

5 For PVT Ltd, Partnership, Ltd, proprietary & individual firms 2% (Or as per Government norms) income tax will be deducted from your each running bill and TDS certificate will be issued to you at the end of each financial year.

6 This work order is being issued to you in duplicate. You are requested to sign one copy and return it to us immediately in token of your acceptance of this work order.

Note: The above mentioned rates are inclusive of all applicable taxes Government Levies, all statutory compliances, charges of local authorities etc. complete. Only GST will be paid extra as applicable

Special Condition:-

1 If it is observed or noticed that you are exceeding the above mentioned rates, please note that the excess amount will be debited to your account. We will not entertain any explanations.

2 The Entire Project duration :-

i) For Rolling Shutter - 3 week from the date of Work Order

ii) For Boom Barrier - 4 week from the date of Work order

3 Transportation of Materials up-to working Place is in Contractor Scope.

4 Design, Preparation of Drawing its approval, manufacturing, packing, loading, transportation, transit insurance, unloading, shifting (site to site), crane required during installation if required & installation complete all work is in your scope of work. We will provide only space for storage. Security of your material is in your scope of work.

5 Scaffolding done by NIHVA , RMKIPL only supply materials on free of Cost.

6 You should follow all safety rules & regulation setup by RMKIPL .

7 You should submit the all statutory documents regarding the safety purpose before starting of work.

8 Warranty for mechanical & electrical parts with maintenance of shutters is for 36 Months.

9 Material should be as per Indian standard code specifications & as per IS 6248.

RMK Infrastructure Pvt. Ltd. **For NIHVA Technologies Pvt. Ltd.**

Gunjankumar Jha

Authorised Signatory **Approved By** **Prepared By** **Contractor Signature**

RMK Infrastructure Pvt. Ltd.

Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507

PURCHASE ORDER

Supplier Details		PO Details	
Name	- **NIHVA Technologies Pvt. Ltd.**	**PO No.**	- RMKPO2021010079
		PO Date	- 13/01/2021
Address	- 187, G- Block, 1st Floor, above Renault Showroom, Thermax chowk, MIDC, Chinchwad, Pune- 411019	**PR No**	- RMK/JIS/PR/2021/0007
		PR Date	- 13/01/2021
		Project Name	- Metjoy Jadhavwadi Gut No 45
Contact Person	- Mr. Arjun Patil		
Mobile No.	- 8551096333	**Site Contact**	-
E-mail	- support@nihva.com	**GST No.**	- 27AAFCR0774G1ZB
GST No.:	- 27AAECN0437H1ZM		

Communication/Billing address	Shipping Address
RMK Infrastructure Pvt. Ltd. Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507	Jadhavwadi Industrial Shed Gate No-45

Sr No.	HSN Code	Description of Item	Unit	Qty	Rate	Disc.	Taxable Amount	Tax Rate	Total
1		Motorized Rolling Shutter 3 x 4 m - - - Design and Supply of Motorized Rolling Shutter as per Following Specification:- B) Technical Specification Sr .No. Specification G I Motorized Rolling Shutter 1 Description: Motorised Rolling Shutter G I Laths with thickness of 1 mm. 2 Mounting Location area Inside area / Outside area 3 Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side 4 Curtain Panel The panel made of 1.0mm thick GI. 5 Curtain panel size 75mm wide 6 Curtain Profile Curved 7 Bottom Profile M. S. Plate 100 mm x 2.5 mm thick with angle stiffener with Rubber Bottom Seal. 8 Side Guide Profile M.S. Special " T" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) 9 Roller Shaft M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h 10 Side Brackets MS Plate 3 mm to 10 mm thick, as per the opening dimension. 11 Hood Cover Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener 12 Surface finish PU paint or Powder coated (RAL code as per approved design from both sides) 13 Drive Unit & Mounting Type Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection 14 Safety Features Safety Catch 15 Actuation By Push Button	NOS	6.0	94,500.00	0.00% 0.00	5,67,000.00	18.00% 1,02,060.00	6,69,060.00

For RMK Infrastructure Pvt. Ltd.

Accepted By

Prepared By

Approved By

NIHVA Technologies Pvt. Ltd.

Subject To Pune Jurisdiction

RMK Infrastructure Pvt. Ltd.

Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507

PURCHASE ORDER

Supplier Details

Name - NIHVA Technologies Pvt. Ltd.

PO Details

PO No. - RMKPO2021010079

Sr No.	HSN Code	Description of Item	Unit	Qty	Rate	Disc.	Taxable Amount	Tax Rate	Total
2		Motorized Rolling Shutter 6 x 5.7 m - - - Design and Supply of Motorized Rolling Shutter as per Following Specification:- B) Technical Specification Sr .No. Specification G I Motorized Rolling Shutter 1 Description: Motorised Rolling Shutter G I Laths with thickness of 1 mm. 2 Mounting Location area Inside area / Outside area 3 Mounting Surface Side Brackets: Optional = On Concrete /Steel & Side 4 Curtain Panel The panel made of 1.0mm thick GI. 5 Curtain panel size 75mm wide 6 Curtain Profile Curved 7 Bottom Profile M. S. Plate 100 mm x 2.5 mm thick with angle stiffener with Rubber Bottom Seal. 8 Side Guide Profile M.S. Special " T" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension) 9 Roller Shaft M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h 10 Side Brackets MS Plate 3 mm to 10 mm thick, as per the opening dimension. 11 Hood Cover Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener 12 Surface finish PU paint or Powder coated (RAL code as per approved design from both sides) 13 Drive Unit & Mounting Type Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection 14 Safety Features Safety Catch 15 Actuation By Push Button	NOS	2.0	2,04,540.00	0.00% 0.00	4,09,080.00	18.00% 73,634.40	4,82,714.40
3		Boom Barrier - - - Design and Supply of Boom Barrier with mobile support as per Following Specification:- B) Technical Specification Boom Barrier Sr .No. Descr iption Specifications 1 Size 4.4 meter 3 Opening time 3S 4 Motor Power Sup ply 24V 5 Type of limit Switch Electronic 6 Safety Photocell sensor, Flashing Light With Buzzer 7 Operated Remote Control / Push Button Pedant	NOS	2.0	82,200.00	0.00% 0.00	1,64,400.00	18.00% 29,592.00	1,93,992.00

Basic Amount	**1,140,480.00**
Total Freight Amount	**0.00**
Total Load/Unload Charges	**0.00**
Total Other Charges	**0.00**
TCS Amount	**0.00**
Total CGST	**102,643.20**

For RMK Infrastructure Pvt. Ltd.

Accepted By

Prepared By

Approved By

NIHVA Technologies Pvt. Ltd.

Subject To Pune Jurisdiction

RMK Infrastructure Pvt. Ltd.

Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507

PURCHASE ORDER

Supplier Details | **PO Details**

Name - **NIHVA Technologies Pvt. Ltd.** | **PO No.** - RMKPO2021010079

Sr No.	HSN Code	Description of Item	Unit	Qty	Rate	Disc.	Taxable Amount	Tax Rate	Total
Total SGST									**102,643.20**
Total IGST									**0.00**
GROSS AMOUNT									**1,345,766.00**

Amount in word : **Thirteen Lakhs Forty Five Thousand Seven Hundred and Sixty Six Only**

Terms And Conditions

Terms and Conditions:-

1) Delivery Schedule

i) As Per Work Order.

2) Payment Condition :-

i) 20 % Against Submission of A) Without dated Security Cheque of same amount B) Shop Drawing submission and approval

ii) 60% After delivery of material at site with Tax invoice and other supporting documents

iii) 20 % After commissioning certificate from RMKIPL's site in-charge for Rolling shutter & Boom Barrier and on submission of A) Original BG valid for 12 Months from commissioning certificate B) Warranty/Guaranty certificate for the Validity of 36 Months from Handing over

3. Above rates are including of all taxes & duties.

4. GST Invoice: Will be required immediately after supply & acceptance of material.

5. Transport: Including.

6. Unloading: Including.

6. Manufacturer Test Certificate will be required along with Supply.

7. Material will be unloaded at site within working hours 9.00 am to 5.00 pm strictly excluding weekly off.

8. M/s. RMK reserves all the rights to reject the material, which will be defective or will not be as per the specifications provided or not delivered within the scheduled time period, without any cost to RMK/Purchaser/Buyer.

9. Please mention our GST No 27AAFCR0774G1ZB in tax invoice & GST return filed by you. In case of any loss due to non-compliance of GST you will indemnify us against any loss/interest/penalty payable due to non-availability of Input Tax Credit.

10. If any dispute arises between the Parties hereto in connection with or related to Purchase Order, such dispute shall be referred to the sole arbitrator appointed by RMK and the venue of the arbitration shall be at Pune. The decision of the Arbitrator shall be final, conclusive and binding upon both the parties.

11. Vendors existing tax payment should be clear to avoid tax/legal issues. Also RMK found any issues in earlier tax payment RMK will hold tax payment (+) safe margin money to avoid legal complications/issues/debits. Also after cleared of vendor's tax payment

For RMK Infrastructure Pvt. Ltd.

Accepted By

Prepared By

Approved By

NIHVA Technologies Pvt. Ltd.

Subject To Pune Jurisdiction

RMK Infrastructure Pvt. Ltd.

Plot No 2992/1, RMK Square,Talegoan Dhabhade, Pune, Maharashtra, India, Pincode- 410507

PURCHASE ORDER

Supplier Details		PO Details	
Name	**- NIHVA Technologies Pvt. Ltd.**	**PO No.**	- RMKPO2021010079

Sr No.	HSN Code	Description of Item	Unit	Qty	Rate	Disc.	Taxable Amount	Tax Rate	Total

RMK will release that payment without any additional cost to RMK/Purchaser/Buyer.

For RMK Infrastructure Pvt. Ltd.

Accepted By

Prepared By

Approved By

NIHVA Technologies Pvt. Ltd.

Subject To Pune Jurisdiction