WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
M/S QUALITY INFRASTRUCTURE PVT LTD	
Address:	
1, RAJHANS COMPLEX, 1ST FLOOR, G.I.D.C., CHAR RASTA, VAPI-396195 STATE:-GUJARAT [24]	

PO Number:	261/QIPL/GUJ/21-22- REVISION-2 Dated-17/02/2022	**W. O. No-**	SO/21-22/0126 R
PO Dated :	05-02-2022	**W. O. Date**	17-02-2022
PO Received Date:	17-02-2022	**Sales Co ordinator**	Pradeep S
Ref. Quotation:	SQT.21.22.0242 R5 DATED-17/02/2022	**Front Sales Person**	Shrikant Mirkute

Dispatch Address:

M/S QUALITY INFRASTRUCTURE PVT LTD C/O DHANUKA AGRTECH LTD PLOT NO-D-3/1/A, DAHEJ-III INDUSTRIAL ESTATE, TA-VAGARA, DAHEJ-392110, DIST-BHARUCH STATE-GUJARAT [24]

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Single Skin Rolling Shutter - Gear Operated** **Size : W 2500 mm X H 3500 mm**	**Description:** Gear Operated Rolling Shutter with GI Slats with thickness of 1.2 mm. **Mounting Location area :** Inside area / Outside area **Mounting Surface:** Side Brackets: Optional = On Concrete /Steel & Side **Curtain Panel:** The panel made of 1.2 mm thick GI **Curtain panel size:** 75mm wide **Curtain Profile:** Curved / Flat - Confirm with client at time of drawing approval . **Bottom Profile:** M. S. Plate 100 mm x 2.5 mm thick with angle stiffener **Side Guide Profile:** M.S." U" Shaped profile **Roller Shaft:** M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h **Side Brackets:** MS Plate 3 mm to 10 mm thick, as per the opening dimension. **Hood Cover:** Made of GI Sheet Thickness 0.6 mm. **Surface finish:** Powder Coated **Drive Unit & Mounting Type:** -Gear Aseembly	Nos	1		Included	-	Pending
2	**Single Skin Rolling Shutter - Gear Operated** **Size : W 3000 mm X H 3500 mm**	Same as above	Nos	4		Included	-	Pending
3	**Single Skin Rolling Shutter - Gear Operated** **Size : W 2000 mm X H 3500 mm**	Same as above	Nos	1		Included	-	Pending
4	**Single Skin Rolling Shutter - Gear Operated** **Size : W 2000 mm X H 3000 mm**	Same as above	Nos	1		Included	-	Pending
5	**Single Skin Rolling Shutter - Gear Operated** **Size : W 2700 mm X H 3500 mm**	Same as above	Nos	1		Included	-	Pending
6	**Single Skin Rolling Shutter - Gear Operated** **Size : W 2500 mm X H 3000 mm**	Same as above	Nos	6		Included	-	Pending
						Total	-	

Non standard items/extra requirement, if any:	

B Commerical Terms:

1	**Payment Terms:**	30% Advance along with PO, 50% before dispatch against P.I and balance 20% will be releaed after 15 days from the satisfactory work completion and measurement certified		
2A	**Delivery Date as per PO:**	Within 4-5 weeks from after drawing approval	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA (Included)	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA	**5B. Loading Charges:**	
6A	**Unloading Scope:**	CLIENT	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT		
11	**GST:**	As Applicable		
12A	**Installation Scope:**	NIHVA	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	No		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	S.M.	G.P.	17-02-2022