NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Fab Lab India
Unit No. 303, 3rd Floor, Bhoomi Velocity, Plot No. B-39A,
Road No. 23, Above ICICI Bank, Wagle Industrial Estate,
Thane – 400604.

Date : 19.12.2020
Quote NO : SQT.20.21.2893
Kind Attn : Harshali Tari
Email Id : enquiry@fablabindia.com
Contact No: 8691001811

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**ASSA ABLOY Make Rapid Roll Up Door HS9020GAT**	2000	2400	4	575,000	2,300,000	20,000	80,000
				Total		**2,300,000**		80,000
2	P&F Charges			3%		**69,000**		
	Total Without Taxes					**2,369,000**		**80,000**
	GST Extra @ 18%			18%		426,420		14,400
	Total With Taxes					**2,795,420**		**94,400**
3	Transportation Charges					**Extra at Actual**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Technical Specification

Albany Make High Speed Door - HS9020GAT



Sr. No	Specification	ASSA ABLOY Make Rapid Roll Up Door HS9020GAT
1	**Area of use:**	Inside
2	**Material:**	Galvanised steel
3	**Colours:**	8 standard colors - white, yellow, green, orange, red, gray, black, blue
4	**Vision Window**	Single row with 400 mm Height
5	**Operating speed:**	Opening: up to 1,2 m/s (optional 2,0 m/s) Closing: 0,5 m/s
6	**Wind load resistance:**	Class 1 (300 Pa (N/m²)) maximum wind load while closing 50 Pa (N/m²)
7	**Water penetration:**	Class 2 (50 Pa (N/m²))
8	**Air permeability:**	Class 1 (24 m³/m²/h at 50 Pa)
9	**Thermal transmittance:**	6,02 W/(m²K)
10	**Lifetime expectations:**	1.000.000 cycles
11	**Temperature working range:**	5 °C to +40 °C
12	**Safety:**	Photocells in side columns
		Flexible soft bottom edge including wireless edge activator
		Break-away and self-repair function

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 12-13 Weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd