NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Jeenali Trading & Comm. Ser. Pvt.Ltd.
103, Safalya Building, DR. Ambedkar Road
Mulund (w) , Mumbai-400080

Date : 07.01.2021
Quote NO : SQT.20.21.2791R1
Kind Attn : **Mr. Manish Mehta**
Email Id : millennium005@gmail.com
Contact No: 9967970333

Project Name & Location: Mumbai

Subject : Quotation for Dock Leveler and Sectional Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Conditions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Automatic Sectional Door Vertical Lift	3000	4000	16	205,000	3,280,000	Inclusive	
2	Dock Leveller 9 Ton	2000	2500	8	190,000	1,520,000	Inclusive	-
				Total		**4,800,000**		-
3	P&F Charges			0%		-		
	Total Without Taxes					**4,800,000**		**-**
	GST Extra @ 18%			18%		864,000		-
	Total With Taxes					**5,664,000**		**-**
4	Transportation Charges					Extra at actual		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	0.1
11	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

NIHVA ASSA ABLOY Sectional Door





Sr. No	Description	Specifications
1	**Model No**	OH1042P
2	**Opening Direction & Mounting**	Vertical
3	**Door produced Based on which certification**	Doors produced according to ISO 9000 or ISO 14000 certified.
4	**Opening/Closing Speed**	0,28 m/s
5	**Door Material**	GI Steel
6	**Panel Thickness**	44 mm
7	**Door sealent**	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	**Water Penetration**	EN 12425 class 3
9	**Air Permealibity**	EN12426 class 3
10	**Wind Load**	EN21424 class 3
11	**Thermal Transittance**	6 W/m2K
12	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	**Emergency Operation**	Single phase 230V direct drive on shaft
14	**Operating Switch**	by Disengagement rope manual
15	**Environmental Green Product DeclarationCertification**	Up/Down Keypad + stopbutton
16	**Drive Unit & Mounting Type**	as per ISO 14025 and EN 15804
17	**Door Safety**	Doors equiped with spring break device; Safety Photo cell, bottom safety edge, rope break mechanism etc.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	
1	Secured and fully covered Store area to keep the material	
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	
3	Electrical Supply on the site single phase/three phase points at different places.	
4	Any civil / masonry/structural work required	
5	All structure support required	
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	
7	Conduits, Cables required	

D) Terms & Conditions

Price : Ex Works Pune

Delivery : For Dock Levellers 5-6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
For Sectional Doors 11-12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with confirmed purchase order; 40% Immediately after delivery of material at site and Balance 10% after Installation

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd