


LOAD DIAGRAM

Nominal static vertical loads are indicated. Value within brackets include dynamic surload factor 1.25 for door leaf loads in open position. Includes items provided by ASSA ABLOY only.





Exterior view, door closed






Exterior view, door open






Force from wire rope hoist
Scale 1:20


MULLION HOIST
LIDAN 1.75T/19TB




Force from mullion wire rope hoist #12. #23 & #34
Scale 1:20



Section thru top beam
Scale 1:20



SECTION A-A



Force by differential pressure transferred to guide rail at each intermediate position. (located at pos 1)
F=23.8 kN

Steel building company in cooperation with door installing company must make a pre-installation load test on the structure, where the mullions are located, in order to simulate the vertical deflection of the structure that occurs when doors are installed. This vertical deflection figure will be used to determine the correct installation level of the mullions. Required material/equipment and personnel by others than ASSA ABLOY.

NOT INCLUDED IN DOOR SUPPLY:

1. Design and supply of all door supporting structural components.
2. Design and supply of all closure between door and adjacent steel.
3. Door jambs adjustable for overall door width and true to plumb.
4. Design and supply of coverage, such as roofing or enclosure, for door components at door head
5. Paint job after completed door installation.
6. Any frameworks being provided by ASSA ABLOY will be clearly indicated as "by ASSA ABLOY".

REQUIREMENTS ON BUILDING:

7. Door head support must be straight within 1/600 of span in the in/out direction and free from protrusions of any kind.
8. For a single door leaf, door head support should be horizontal and straight within 1/600 of span at distributed full door load.
9. Door side jambs must be smooth, straight and parallel, out of plumb must not exceed 2mm/m (total deviation at full length 5 mm) in any direction.
10. Any footings at bottom of jamb columns must not interfere with installation of guide rails at floor level.
11. At time of installation, finished floor, free from obstructions, out to a distance of 2 m on each side of door centreline must be available.

DOOR PROPERTIES:

12. The door is designed to withstand a differential pressure of 1.33kPa.
14. Mullions #12 & #34 and mullion pits are designed to allow for 97mm of downward deflection and 97mm of upward deflection due to external loads such as wind.
15. Mullion #23 and mullion pit are designed to allow for 137mm of downward deflection and 137 mm of upward deflection due to external loads such as wind.
16. Guide rails, top- and intermediate beams in extruded aluminium with natural finish.
17. Environmental category: Megadoor standard
18. Bottom beams & Mullions carbon steel painted: Light grey (RAL7047)
19. Colored clamp strips on both sides: Inside.Translucent (RAL9010). Outside. White (RAL 9016)
20. The door fabric is a UV stabilized, flame retardant, self-extinguishing, PVC coated polyester fabric with fire technical properties Euroclass C-s2, d0 (according to EN 13501-1:2007). Colour of fabric: Inside. TRANSLUCENT WHITE (RAL 9010) Outside. WHITE (NCS 0500, RAL 9016)

ELECTRICAL:

21. One main control panel provided of PLC type + extra screen.
22. Control mode : Impulse up / Constant contact down.
23. Cables are included.
24. Back-up power socket & switch.
25. Audible & visual alarm.
26. Approx. size of main control panel: WxHxD (500mm x 600mm x 250 mm),
27. Location of main control panel: Please specify location.
28. Aux. Voltage 24VDC
29. Power supply: 400V /3Ph /50Hz
30. Power: 31.2kW
31. Nom. current: 64.8A
32. Start. current: 71.3A
33. (max. allowed voltage drop at start: 5%)

DOOR HOIST UNIT:#1, #2, #3 & #4
LIDAN 4.9T2/27
2x Ø12mm wire ropes. Rupture load 100 kN/rope.

MULLION HOIST #12, #23 & #34
LIDAN 1.75T/19 TB
Ø 10mm wire rope for normal operation. rupture load of 69.8 kN/rope.
Ø 10mm idling wire rope for arresting operation. rupture load of 69.8 kN/rope.

DOOR IDENTITY NUMBER: 84247001

INTERFACE DRAWING, ref. to drwng. no. 65845

DESIGNED PL		SIZE A1	SCALE 1:200
CODE 84247		If not otherwise stated: Tolerances ISO 2768-m EN ISO 13920-B	
ITEM NO		Cutting class ISO 9013-442	
DATE 2018-02-23		Weld class ISO 5817-C	
ASSA ABLOY		Surface finish Smooth raw surface	

Indamer
India
Megadoor 82000 x 14200/13500
Load diagram & Notes

DRAWING NO 65846 | REVISION B | PLOT DATE

This document is the property of ASSA ABLOY Entrance Systems AB and shall not without our written permission be copied, imparted to a third party or used for any other unauthorized purpose.