NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/2175R1 **Date :11-10-2019**

ALDECOR INTERIORS PVT LTD.
39/2(O), KALYANI GARDEN, GANGAMMA TEMPLE STREET,
ASHOK NAGAR, BSK 1ST STAGE, BANGALORE - 560050.

Kind Attention : Gowthami M
Email : gowthami@aldecorindia.com
Contact No :

Project Name And Location : Bengaluru

Subject : Quotation for Automatic Revolving Door

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer :-

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Automatic Revolving Door (Besam - ASSA Abloy)** **(100% Imported Besam Drive – made in Europe)**				



1 .**General Details** :
-Internal Diameter - 2200 mm
-Internal Height - 2200 mm
-Canopy Height - 200 mm
-Total Height -2400 mm
-Revolving Doorset - 4 Door Leaves
-Rigid Doorset with Fixed Leaves
-Design - Door Leaves: Besam "frame" profile feature soft edge rubber nosing & brush carrier
- Rotating section: Satin Silver Anodised
-Automatic Drive : Control Unit built in behind the fascia above the inside entrance.
-Micro Processor controlled with plug in modules and LED status lights
- Speed Control : Vertical Safety Switches
- Glass Wall : 4+4 mm Clear Laminated Frame
- Door Section made from Aluminium profiles
- Ceiling made from white laminated panels
- Dust protection roof made from white laminated Panels -
- Power supply: 230 V, 50 Hz, mains fuse max 10 A, 100-120 V, 50/60 Hz, mains fuse max 16 A
-Power consumption: max. 400 W
-Lighting : 12 V, 120 W

2. Safety Features :
- If an obstacle prohibits the rotation of the door (the resistance is higher than the pre-set value)the rotation will cease
- Compressible vertical safety switches placed on the drum edges
-Emergency stop

	1	Revolving Glasss Door - 4 Leaves Size : (W)2200 x (H)2400 mm **(Supply + Installation)**	11	No.	3,207,000	35,277,000
		Total Amount				**35,277,000**

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% supply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	15 - 16 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before delivery
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	Extra @ Actual
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat o**n **7219207333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd