NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ITC
kapoorthala (punjab)
GST No.03AAACI5950L2ZJ

Date : 18.06.2020
Quote NO : SQT.19.20.2351R
Kind Attn : Gaurav Kumar
Email Id : Gaurav.Kumar@itc.in
Contact No: **9736291336**

Project Name & Location: Bowl feeder and Belt conveyor, Punjab

Subject : Quotation for Bowl feeder and Belt conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
			(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Belt Conveyor	(L) 500 mm x (W) 150 mm	1	77,300	77,300	**35,000**	
2	Bowl Feeder		1	2,30,700	2,30,700		
3	PLC, PLC Analog Output, Incremental encoder, HMI, Accessories		1	71,120	71,120		
			Total		**3,79,120**	**35,000**	
4	P&F Charges		3%		**11,374**		
	Total Without Taxes				**3,90,494**	**35,000**	
	GST Extra @ 18%		18%		70,289	6,300	
	Total With Taxes				**4,60,782**	**41,300**	
5	Transportation Charges				**In Client Scope**		
6	Unloading Charges @ Site				**In Client Scope**		

B) Technical Specification

i) Bowl feeder -

Material-S.S. 202

Outlet-Single

Coil- 4 Nos / 1 Nos

Feed rate- 80 piece /minute.

ii) Belt conveyor -

Size : (L) 500 mm x (W) 150 mm

Material Contact Part : SS304

Structure : MS Powder Coated

Conveyor Speed : 15 mtr/min

This Include -

1. PLC
2. PLC Analog Output
3. Incremental encoder
4. HMI
5. Accessories

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Installation will start after receiving of Site Readyness Photographs or written Email communication.
2. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4. If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 8- 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shailendra Saindane on 7709209333**

With Best Regards
Yogita
8530872333
For NIHVA Technologies Pvt Ltd