| PORTABLE SCISSOR LIFT-MANUAL HAND OPERATED TYPE | | | |
|---|---|---|---|
| CAPACITY - 100KG | | | |
| PLATFORM SIZE- 1000WX1500L | | | |
| CLOSE HEIGHT - 450 MM | | | |
| MAXIMUM HEIGHT FROM GROUND- 1950 MM | | | |
| LIFT HEIGHT -1500 MM | | | |
| FEATURES - DETACHABLE SAFETY RAILING WITH DOOR OF HEIGHT 500 MM | | | |
| **SR NO** | **ITEM** | **DESCRIPTION** | **COST** |
| 1 | FABRICATION COST | M.S. RAW MATERIAL WEIGHT - 400 KG | 36000 |
| 2 | HANDPUMP | DOWTY/STD MAKE | 15000 |
| 4 | HYDRAULIC CYLINDERS | 1 NO OF CYINDER BORE 30 MM STROKE 1000MM | 8000 |
| 5 | HOSES & CONNECTOR | STD AS PER REQUIRED | 3000 |
| 6 | HYDRAULIC OIL | STD AS PER REQUIRED | 700 |
| 8 | MACHINING & PLATES | STD AS PER REQUIRED | 7000 |
| 9 | PAINTING | 5 LITRE APPROX. | 4100 |
| 10 | CASTOR WHEEL | | 3000 |
| 11 | MISCELLANEOUS | LABELS , ETC | 1000 |
| 12 | INTERNAL TRANSPORT | | 1000 |
| | | **MANUFACTURING COST IN INR** | 78800 |
| PREPARED BY - SIDDHESHWAR SHELAKE | | | |