NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shapoorji Pallonji And Company Private Limited
7th Floor, Surya Chambers, No. 124, HAL Airport Road,
Murugeshpalya, Bangalore – 560017.

Date : 09.12.2019
Quote NO : SQT.19.20.2183R
Kind Attn : Ms. PRIYA KUMBAR
Email Id : PRIYA.KUMBAR@shapoorji.com
Contact No: **080 66213500**

Project Name & Location: IKEA, Bangalore

Subject : Quotation for Sliding Glass Door, Sectional Door, High Speed Door, Dock Leveller, Dock Shelter, Dock House

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sliding Glass Door (ASSA ABLOY)	2000	2100	5	2,15,000	10,75,000	20,000	1,00,000
2	Sliding Glass Door (ASSA ABLOY)	2400	3000	3	2,32,000	6,96,000	20,000	60,000
3	Sectional Door (ASSA ABLOY)	3100	3800	2	2,27,000	4,54,000	20,000	40,000
4	Sectional Door (ASSA ABLOY)	3200	3200	5	2,18,000	10,90,000	20,000	1,00,000
5	Sectional Door (ASSA ABLOY)	3650	3800	8	2,35,000	18,80,000	20,000	1,60,000
6	High Speed Door ((ASSA ABLOY) HS9020G)	3500	3500	1	5,49,000	5,49,000	20,000	20,000
7	High Speed Door ((ASSA ABLOY) HS9020G)	3800	3800	3	6,50,000	19,50,000	20,000	60,000
8	High Speed Door ((ASSA ABLOY) HS9020G)	2000	2500	1	4,40,000	4,40,000	20,000	20,000
9	High Speed Door ((ASSA ABLOY) HS9020G)	2500	2500	1	4,53,000	4,53,000	20,000	20,000
10	High Speed Door ((ASSA ABLOY) HS9020G)	3100	3200	1	5,44,000	5,44,000	20,000	20,000
11	High Speed Door ((ASSA ABLOY) HS9020G)	3500	3600	1	6,01,000	6,01,000	20,000	20,000
12	Dock Leveller (ASSA ABLOY)	2000	2500	5	3,10,000	15,50,000	20,000	1,00,000
13	Dock Leveller (ASSA ABLOY)	2000	3500	8	3,78,000	30,24,000	20,000	1,60,000
14	Dock Shelter (ASSA ABLOY)	3300	3300	13	1,17,000	15,21,000	20,000	2,60,000
15	Load House (ASSA ABLOY)	3100	3800	13	3,15,000	40,95,000	20,000	2,60,000
				Total		**1,99,22,000**		**14,00,000**
			P&F Charges	3%		**5,97,660**		
			Total Without Taxes			**2,05,19,660**		**14,00,000**
			GST Extra @ 18%	18%		36,93,539		2,52,000
			Total With Taxes			**2,42,13,199**		**16,52,000**
16			Transportation Charges			**In Client Scope**		
17			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Automatic Sliding Glass Door






Sr. No.	Description	Specification
1	Power Supply	100-240 VAC ±10% 50/60 Hz
2	Power consumption	max. 250 W
3	Open and closing speed variable	up to 1.7 m/s (2 leaves)
4	Hold-open time	0 – 60 s
5	Ambient temperature	- 20°C to + 50°C
6	Relative humidity (non-condensing)	max. 85%
7	Operator type	Bi part operator
8	Glass	10mm thick toughened glass

ASSA ABLOY Motorised Sectional Door







Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Standard
4	Opening/Closing Speed	CDM9 0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm Square Grid, steel sheet
7	Filling	CFC-free polyurethane
8	Panel colour	RAL 9002 Grey White Powder coated
9	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
10	Panel Flame Retardent standrad	Flame retardant polyurethane foam according DIN4102-class B2.
11	Water Penetration	EN 12425 class 3
12	Air Permealibity	EN12426 class 3
13	Wind Load	EN21424 class 3
14	Thermal Transittance	EN 12428 1.10W /m2K
15	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
16	Door saftey	Doors equiped with spring break device
17	Incase of Power failuer	Doors to be equiped with quick release fuction
18	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
19	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
20	Emergency Operation	by Disengagement rope manual
21	Operating Switch	Up/Down Keypad + stopbutton
22	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
23	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

ASSA ABLOY Make Rapid Roll Up Door HS9020G




HS9020G



SIDE GUIDES




Safety Facilities



Sr. No	Description	Specification
1	Area of Use	Interior applications.
2	Drive System	Gravity Driven System
3	Opening Speed	up to 2.0 m/s depending on size of door.
4	Closing Speed	up to 0.5 m/s depending on size of door.
5	Photocells	Inside Columns
6	Safety	• Flexible soft bottom edge including wireless edge activator. • Break-away and self-repair function.
6	Wind Load Resistance	(EN 12424) Class 1 (300 Pa (N/m^2)). Maximum wind load while closing 50 Pa (N/m^2)
7	Water Penetration	(EN 12425) Class 2 (50 Pa (N/m^2)) 20 minutes water spray
8	Air Permeability	(EN 12426) Class 1 (24 $m^3/m^2/h$ at 50 Pa)
9	Thermal Resistance	(EN 12428) 6,02 $W/(m^2K)$
10	Temperature Working Range	5 °C to +40 °C
11	Door Curtain	900 g/m^2 colored PVC, Flexible door curtain without ridged parts
12	Various Window	400 mm height single row
13	Operator	220V - 240V 1-phase 0,75 kW 16A
14	Operator Protection	IP65. Soft start/stop significantly prolongs motor lifespan.
15	Control Unit Protection	IP54
16	Lifetime Expectations	1,000,000 cycles
15	Side Column	Unique side column technology provides excellent seal on all 4 sides thereby reducing heat loss
16	Lifetime Expectations	1,000,000 cycles
15	Control Unit Protection	IP54
16	Motor	The motor with frequency converter guarantees smooth and reliable operation.
15	Control Unit Protection	Control unit with display, impulse Up and Down buttons, an emergency stop mushroom button and a mechanical main switch.
16	Lifetime Expectations	1,000,000 cycles

ASSA ABLOY Dock Leveller (DL6010S)







Safeguard emergency stop with two cylinders

Sr. No.	Description	Specification
1	Load Capicity	6 Ton
2	Size (W X L)mm	2000 X 2500 & 2000 X 3500
3	Platform Tear- Plate thickness	6/8mm - 8/10mm
4	Lip material & Length	Steel, 400/500mm
5	Control Unit protection Class	IP54
6	Temperature rangr hydraulic oil	- 20 °C to + 60 °C
7	Magnetic Valves	24v/DC 18W S1
8	Nominal Voltage	400V 3 Phase
9	Nominal motor power	0.75kw

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

ASSA ABLOY Retractable Dock Shelter (DS6060A)



ASSA ABLOY Retractable Dock Shelter



Docking System (Sectional Door, Dock Leveler, Dock Shelter)

Sr. No.	Description	Specification
1	Size (W X H)mm	3300 X 3300
2	Nominal depth	600, 900 mm
3	Top curtain	1000mm
4	Side Curtain	600mm
5	Curtain Color	Black
6	Parking Guide	White, Yellow
7	Wall fixings	Concrete, sandwich, light concrete, load house, cavity, insulated pannel
8	Top & Side curtains	Double layer high quality polyster
9	Thickness	3mm
10	Continous Roof Cover	one layer high quality polyester
11	Thickness	0.5mm
12	Flammibility all curtains	DIN 75200

ASSA ABLOY Load House (LH6080L)



Sr. No.	Description	Specification
1	Size (W X H)mm	3100 x 3800
2	Thickness of material	0.6 Profile steel sheet
3	Surface Treatment	Hot diped galvanised
4	Basic Wind Load	0.84kN/m²

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 13-14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd