NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Takshi Auto Components Pvt. Ltd.
Bhamboli, Chakan

Date : 28.04.2023
Quote NO : MHE_22.23.0025R1
Kind Attn : Mr. Ravindra Samudra
Email Id : ravindra.samudra@takshiauto.com
Contact No: 9881007403

Project Name & Location: Bhamboli Plant, Chakan

Subject : Commercial Offer for Floor Monuted Hydraulic Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Floor Monuted Hydraulic Scissor Lift** • Capacity 2000 Kg • Lifting Height: 2000 mm • Close height: 500 mm	2430 L mm X 2130 W mm	1	4,65,000	4,65,000	15,000	15,000
			Total		**4,65,000**		**15,000**
			Total Without Taxes				**4,80,000**
2	GST Extra @ 18%		18%				**Extra At Actual**
3	P&F Charges on Total Supply Value		3%				**Included**
4	Transportation Charge						**In NIHVA Scope**
5	Unloading Charges @ Site						**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Floor Monuted Hydraulic Scissor Lift

Sr. No	Description	Specifications
1	**Capacity**	2000 Kg
2	**Platform size**	(L) 2430 mm X (W) 2130 mm
3	**Shut Height**	500 mm
4	**Lift Height**	2000 mm
5	**Lip size**	One side, Manual Size: 350mm
6	**Railing**	2-Side Detachable Railings, Height 900 mm
7	**Type of platform**	Chequred plate with 8mm thickness
8	**Motor**	Siemens
9	**Pump**	Rexroth
10	**Push Button**	Teknik

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of site readiness photographs or written email communication.

2 For any reason if we need to stop our Installation and demobilize the team without completing the work, then extra cost will be applicable for remobilizing the team.

3 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA which is at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material.
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil/masonry/structural work required.
5	All structure support required.
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required.

D) Terms & Conditions

Price :	Ex Works Pune.
Delivery :	5-6 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval excluding selling period.
Payment :	50% Advance along with Confirmed Purchase Order. 40% Against proforma invoice before dispatch of material at site. 10% After of Installation.
Validity :	Validity of Offer is 7 days from the date of quotation
Warranty :	12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd