NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1713R **Date : 26.06.2019**

Shree Renuka Sugars Limited
Survey No.178/1, AT & Post : Bharapar,
, Tal. Gandhidham , Kutch – Gujarat, India.

Kind Attn: Kishor Patel
Email: kishorkumar.patel@renukasugars.com>
Contact No: 6359001488

Project Name And Location :

Subject : Quotation for Full Height Turnstile Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :

Option 1 :-

Sr No	Description	Qty	Unit	Rate In INR	Net Amount INR
	Single Sided Full Height Turnstile Gate: • It has zero position of self -checking, easy for users to maintain and use. • There is alarm notice funtion when illegal access. • Avoid bump funtion: When the turnstile does not receive the open signals, the baffle will lock automatically. • IR/mechanical dual anti-lined funtion: When the baffle has problem in reseng, it will stop working automatic ally in certain time, and the potency is small, will make an alarm sound at the same time. • Resengautomatically: the passenger read effectively, the system will cancel this access authority if they will not access in certain time. • Standard wiring connection: can connect with many kinds of card readers, and can remote control through the computer. • The whole system works steadily, and the noise is very low. lock time: 0.2s; Pass rate: 35 person/min each from both gates; Pass Width: 500-700mm; Input: 100V~240V; Driving Voltage: 24v; Environment: -20~60°c; Power Consumption: 35w; Weight:220kgMake				
1	Full Height Turnstile Gate (Supply + Installation+)	4	No	385,000	1,540,000
2	Access control machine with 3000 user capacity (Bio + Card)	4	No	22,000	88,000
	Total				**1,628,000**

GST Pune : 27AAECN0437H1ZM	**Total** **1,628,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex. Works Pune
2. **P & F Charges** **:** @ 3% of Total supply value
3. **Freight Notes** **:** Extra as applicable
4. **Delivery** **: 5 - 6** weeks from the date of receipt of confirmed purchase order, Advance Payment and Drawing approval.
5. **Payment** **:** 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6. **Insurance** **:** Extra As applicable
7. **Tax** **:** GST @18%
8. **Validity** **:** Validity of Offer is 15 days from the date of quotation.
9. **Warranty** **:** 12 months from the date of supply.

Please feel free to Contact **Mr. Swapnil Kulat** on **07219207333** For any further Clarification / Information in this Concern.

With Best Regards

Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd