NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Progressive infra project Pvt. Ltd.
2nd Floor, Sai Niketan,
S. No.31/ 1A/2-C, Opp. Mega Mart
Old Pune -Mumbai Highway , Dapodi, Pune- 411012

Date : 11.10.2019
Quote NO : SQT.19.20.2142R
Kind Attn : Pooja Rachmale.
Email Id : pip.ipl.pune@gmail.com
Contact No: 022-26852233

Project Name & Location: GKN, Pimpri.

Subject : Quotation for Gear Operated Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Gear Operated Rolling Shutter**	3000	4500	7	70,000	490,000	Installation Charges included in Supply	
				Total		**490,000**		-
2			P&F Charges	3%		**Nil**		
			Total Without Taxes			**490,000**		-
			GST Extra @ 18%	18%		88,200		-
			Total With Taxes			**578,200**		-
3			Transportation Charges			**Included**		
4			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	MS Gear Operated Rolling Shutter
1	Description:	Gear Operated Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	Operation	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order, 40% after material received on site & 10% immediate after installation.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Ulka Auti
72519206333
For NIHVA Technologies Pvt Ltd