NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1860 **Date : 25-07-2019**

Ratnarup Projects Pvt Ltd.
202/203 Amar Neptune , Baner Road ,
Near Sai Banglow.
Baner , Pune.

Kind Attn: Mr. Satish Pardeshi.
Email: satish@ratnarupprojects.com
Contact: 7722013837

Project Name And Location : Kingfa, Chakan.

Subject : Quotation for Boom Barrier

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Boom Barrier** **Size - (L)6000 mm** **TECHNICAL SPECIFICATIONS** **• Power supply: 230V±10% 50/60Hz(*)** **• Power absorbed: 300W** **• Absorption (with accessories): 1A** **• Internal lubrication: permanent grease** **• Max torque: 600 Nm** **• Impact reaction: encoder** **• Type of boom: rectangular/round** **• Limit devices: Electrical incorporated & adjustable** **• Working temperature: from -20°C to +55°C** **• Degree of protection: IP 54** **• Operator weight (without boom): 58 Kg (MICHELANGELO BT A 60)** **• Mains/low voltage insulation: > 2MOhm 500V** **• Dielectric strength: mains/low voltage 3750V~ for 1 minute** **• Motor output current: 25A max (MICHELANGELOBT A 60)** **(Supply + Installation)**				
1	Size 6 Mtr	2	No	140,000	280,000
Total					280,000

GST Pune:	27AAECN0437H1ZM

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry / structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provide structure drawing only if required
5. Existing / Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3 % of total Supply Value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	3-4 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	Extra @ 18 %
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain** on **08551092333** For any further Clarification /Information in this Concern.

With Best Regards

Ulka Auti
7410179333
For NIHVA Technologies Pvt Ltd