NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Central Public Works
GOA CENTRAL SUB DIVISION –IV
CENTRAL PUBLIC WORKS DEPARTMENT
NEAR HOLY CROSS CHURCH ,BAMBOLIM GOA- 403202

Date : 12.10.2020
Quote NO : SQT.20.21.2757
Kind Attn : Varad Salake
Email Id : varadsalke@gmail.com
Contact No: 8130114549

Subject : Quotation for Single Skin Aluminium Rolling Shutter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Single Skin Aluminium Rolling Shutter**	2600	3000	8	444,000	3,552,000	Inclusive	
				Total		**3,552,000**		-
2				P&F Charges	3%	106,560		
				Total Without Taxes		3,658,560		-
				GST Extra @ 18%	18%	658,540.80		-
				Total With Taxes		**4,317,101**		-
3				Transportation Charges		**Inclusive**		
4				Unloading Charges @ Site		**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Single Skin Aluminium Rolling Shutter

Specification	Single Skin Aluminium Rolling Shutter
Standard Surface finish	The standard surface finish for unheated buildings where the shutters appearance is not a primary concern. Coil-coated aluminium. High-quality colour coating as long-term weather protection on the outside of the profile ensuring an attractive appearance over many years. The additional protective paint containing polyamide particles reduces friction and minimises the noise produced by the shutter action.
Aluminium Guide	Aluminium guide rails with guide channel, black plastic runner
Bottom Profile	Extruded Double skin aluminium bottom profile , Lintel seal, Bottom seal made of EPDM profile, Need to use both side Tension springs for Counterbalancing the shutter, Ready-to-fit shaft German make operator,
Power input	1- phase current 0.25 kW, Protection category IP 65 (jet-water protected)
Safety Features	Integrated anti drop device / safety Brake , Integrated microprocessor control along with operator, Adjustable force limit, Connection cable with CEE male plug in protection category IP 44
Standard accessories	Chain Hoist to operate shutter manually and electrical operating mode through Pushbutton – for automatic door, Soft start and soft stop, Ensures quiet door travel, reducing wear on the door and operator.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 12 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Transportation : 4000/- / Unit (Shutter) is consider on as per todays. Calculation at Actual varies depend on quantity and order place date.

Please feel free to Contact **Mrs. Sneha Bharane on 8551035333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd