NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Ti Tensile
Delhi

Date : 01.05.2021
Quote NO : RR_21.22.0012
Kind Attn : Mr. Ajay Khanna
Email Id : titensile@gmail.com
Contact No: 9818185152

Project Name & Location: Movable Roof Enclosures, Mumbai

Subject : Commercial Offer for Movable Roof Enclosures

Dear Sir / Ma'am,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size (mm)	Qty	Supply Charges in INR	
			(Nos)	Unit Price	Total Amount
1	**Movable Roof Enclosures (Drive-Manually)** Fixed Cover (Top & Vertical side) 1200 X 8000 mm	• 6150 X 14300 X 3480 (7 Panels) • Fixed vertical & horizontal Panel	1	33,55,000	33,55,000
2	**Installation Charges of Movable Roof Enclosures**		1	1,75,000	1,75,000
			Total		**35,30,000**
		GST Extra @ 18%	18%		**6,35,400**
		Total With Taxes			**41,65,400**
3		Transportation Charges			**Extra At Actual**
4		Unloading Charges @ Site			**In Client Scope**

B) Technical Specification -

1. Polycarbonate Compact Clear/Embossed 4.0 mm Thick
2. Centre Opening (4 Segment one side and 3 segment other side)
3. Guide : Annodized AL Guide
4. Interlocking
5. All MS Framework required for the enclosure included **a) MS SHS 50X50X3 - TOP SHS - TRACK PLATE SUPPORT** **b) MS PLATE 650X3 - TOP PLATE - TRACK FASTENER PLATE** **c) MS PLATE 600X6 - BOTTOM PLATE – TRACK FASTENER PLATE** **d) MS PLATE 500X3 - BRACKET – WALL MOUNTING** **e) MS SHS 100X100X6 - BRACKET – TOP SUPPORT SHS** **f) MS SHS 50X50X6 - BRACKET STIFFENER** **g) MS L ANGLE 50X50X6 - BRACKET BASE FRAME** **h) MS SHS 150X150X4 - COLUMN + BEAM FOR LEVELLING OFFSET**
6. EPDM Gaskets and sealants
7. SS Fastners
8. UV Protected both sides.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.

Note: Please find below List which are in Client Scope

Sr. No		Remark
1	Secured and fully covered Store area to keep the material.	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	All structure support required.	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.
Payment	: 65% advance along with PO, 35% before dispatch after material readiness.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 10 years warranty for polycarbonate sheets, 5 years on Aluminium Structure and 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd