NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Laxmi snacks
Nadiad, Gujarat

Date : 24.02.2020
Quote NO : SQT/19-20/2461
Kind Attn : Mr. Sunil Patel
Email Id : civil.nadiad@realnamkeen.com
Contact No: 7600992521

Subject : Quotation for Sectional Door and Rolling Shutter.(Project -Realnamkeen)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	Option -1							
1	**MS Gear Operated Rolling Shutter**	4750	2550	1	76,000	76,000	20,000	20,000
2	**MS Gear Operated Rolling Shutter**	3050	2550	1	65,000	65,000	20,000	20,000
3	**GI Gear Operated Rolling Shutter**	2500	3000	2	55,000	110,000	20,000	40,000
4	**GI Gear Operated Rolling Shutter**	2500	3050	1	56,000	56,000	20,000	20,000
5	**GI Motorized Rolling Shutter**	4365	5330	1	144,000	144,000	20,000	20,000
				Total		**451,000**		**120,000**
	Option -2							
1	**Sectional Door**	4750	2550	1	286,000	286,000	20,000	20,000
2	**Sectional Door**	3050	2550	1	257,000	257,000	20,000	20,000
3	**Sectional Door**	2500	3000	2	258,000	516,000	20,000	40,000
4	**Sectional Door**	2500	3050	1	260,000	260,000	20,000	20,000
5	**Sectional Door**	4365	5330	1	351,000	351,000	20,000	20,000
				Total		**1,670,000**		**120,000**
6	P&F Charges			3%				
	Total Without Taxes							
	GST Extra @ 18%			18%		-		-
	Total With Taxes					**-**		**-**
7	Transportation Charges					In Client Scope		
8	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr .No.	Specification	Sectional Door -Crawford - NIHVA Assaabloy	
1	**Opening/Closing Speed**	0.25 m/s	
2	**Door Material**	GI Steel with PUF inside	
3	**Panel Thickness**	42mm	
4	**Panel colour**	RAL 9002 Powder coated	
7	**Broken cold bridge**	Section joints with broken cold bridges	
8	**Door sealent**	All door sealants made of EPDM rubber.	
9	**All Panel height**	All panels should be 545mm high	
10	**Panel Inside insulation metrial**	Insulation material to be CFC free polyuretane foam.	
11	**Panel Flame Retardent standrad**	Flame retardant polyurethane foam according DIN4102-class B2.	
12	**Steel component Material**	All steel components to be electro galvanized	
13	**Hinge Material**	Glass fibre reinforced Polyamide	
14	**Panel Thickness**	42 mm	
15	**Spring Material surface finish**	Powder coated	
16	**Water Penetration**	EN 12425	class 3
17	**Air Permealibity**	EN12426	class 2
18	**Wind Load**	EN21424	class 3
19	**Thermal Transittance**	EN 12428 1.10W /m2K	
20	**Bottom sealing**	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber	
21	**Incase of Power failuer**	One can operate the Door manually	
22	**Operator power conumption**	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W	
23	**Drive Unit & Mounting Type**	Single phase 230V direct drive on shaft	
24	**Emergency Operation**	by Disengagement rope manual	
25	**Operating Switch**	Up/Down Keypad + stopbutton	
Sr .No.	**Specification**	**MS Gear Operated Rolling Shutter**	
1	**Description:**	Gear Operated Rolling Shutter with MS Laths with thickness of 1 mm.	
2	**Mounting Location area**	Inside area / Outside area	
3	**Mounting Surface**	Side Brackets: Optional = On Concrete	
4	**Curtain Panel**	The panel made of 1.0mm thick MS.	
5	**Curtain panel size**	75mm wide	
6	**Curtain Profile**	Curved	
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener	
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)	
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h	
10	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener	
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer	
12	**Operation**	Gear Assembly.	

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description:**	Gear Operated Rolling Shutter with GILaths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly.

Sr .No.	Specification	GI Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Side Brackets: Optional = On Concrete /Steel & Side
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain on 855192333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd