NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Meinhardt EPCM India Pvt Ltd.
ITC Green Center , No. 18 , Banaswadi Main Road
North Tower, 4th Floor(West Wing) , Maruthiseva Nagar
Bangalore – 560005
India.

Date : 13.08.2019
Quote NO : SQT.19.20.1923
Kind Attn : Mr. Logesh
Email Id : logesh.sp@meinhardtgroup.com
Contact No: +91-948-620-2338

Subject : Offer for on going projects across India

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Truck Tilting Unit Capacity 60 Mt	3000	12000	1	2,187,500	2,187,500	150,000	150,000
2	Automatic Sliding glass door	1200	2200	1	260,000	260,000	20,000	20,000
3	Bollards			1	242,500	242,500	18,000	18,000
			Total			**2,690,000**		**188,000**
4	P&F Charges			3%		**80,700**		
	Total Without Taxes					**2,770,700**		**188,000**
	GST Extra @ 18%			18%		498,726		33,840
	Total With Taxes					**3,269,426**		**221,840**
5	Transportation Charges					**In Client Scope**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1 Truck Tilting Unit

- Material to be Unload: Free Flowing Material
- Weight to be Unload : 40 T
- Vehicle Type : Long Truck Tata 16 , 25, 37 Series Model
- Platform Size – 3 Mtr x 12 Mtr Long
- Cycle time - Approx. 60 Min.
- Tilting angle 55 Degree
- Vehicle clamping by Hydraulic cylinders
- Platform tilting by Hydraulic cylinders.
- Vehicle enter on platform in reserve direction.

2 Sliding Glass Door

- Green Environmental Certification : ENVIRONMENTAL PRODUCT DECLARATION as per ISO 14025 and EN 15804
- Complies with the following directives: 2014/30/EU ElectroMagnetic Compatibility Directive (EMCD) & 2006/42/EC Machinery Directive (MD)
- Harmonized European standards which have been applied: EN 61000-6-2:2005 EN 61000-6-3:2007+A1 EN ISO 13849-1:2008EN 16005:2012 EN 60335-1:2012 EN 60335-2-103 2003+A1:2009
- Operator dimensions (h) 150 mm x (d) 123 mm : height x depth
- Power supply 100-240 VAC ±10% 50/60 Hz : 100-240 VAC ±10% 50/60 Hz
- Power consumption max. : 250 W

3 Bollards

- Supply Voltage: 230V
- Work Type: Intensive Use - 1500 movents/Day
- Opening Time: 9 Sec
- Impact Registance : 10,500 Joules
- Brake - in proof : 150,00 Joules
- Operating temperature : - 20 ' C to + 60 ' C

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd