**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**HIRANANDANI COMMUNITIES**
Mumbai
Maharashtra -India.

**Date : 13.10.2020**
Quote NO : SQT.20-21_0055R
**Kind Attn :** Mr. SILAMBHARASAN. P
Email Id : psilambarasan@hrealty.com
Contact No: 8939828669

**Subject : Quotation for Sliding Gate & Boom Barrier**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | AUTOMATIC SINGLE LEAF BI-PARTING SLIDING GATE | 17000 | 1800 | 1 | 7,40,000 | 7,40,000 | 20,000 | 20,000 |
| 2 | AUTOMATIC SINGLE LEAF SLIDING GATE | 9000 | 1800 | 1 | 4,25,000 | 4,25,000 | 20,000 | 20,000 |
| 3 | AUTOMATIC SINGLE LEAF SLIDING GATE | 6000 | 1800 | 1 | 3,50,000 | 3,50,000 | 20,000 | 20,000 |
| 4 | AUTOMATIC BOOM BARRIER | 8000 | | 2 | 2,31,000 | 4,62,000 | 20,000 | 40,000 |
| 5 | AUTOMATIC BOOM BARRIER | 6000 | | 1 | 1,40,000 | 1,40,000 | 20,000 | 20,000 |
| 6 | AUTOMATIC BOOM BARRIER | 4500 | | 2 | 1,30,000 | 2,60,000 | 20,000 | 40,000 |
| | | | **Total Value** | | | **23,77,000** | | **1,60,000** |
| 7 | | | **P&F Charges** | 0% | | - | | |
| | | | **Total Without Taxes** | | | **23,77,000** | | **1,60,000** |
| | | | GST Extra @ 18% | 18% | | 4,27,860 | | 28,800 |
| | | | **Total With Taxes** | | | **28,04,860** | | **1,88,800** |
| 8 | | | Transportation Charges | | | **Included in above price** | | |
| 9 | | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) Technical Specifications**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Door type | Motorised Sliding Gate |
| 2 | Clear Opening gate dimension | 1) (W) 17000 mm X (H) 1800 mm<br>2) (W) 9000 mm X (H) 1800 mm<br>3) (W) 6000 mm X (H) 1800 mm |
| 3 | Opening Direction | Horizontal - from left to right or reverse |
| 4 | Mounting Location area | Inside area |
| 5 | Design Pattern | Standard Tubular Design Pattern |
| 6 | Outer Frame Tube Sizes | 80 x 80 x 3.2mm MS SQ. TUBE |
| 7 | Internal Vertical Tube Sizes | 30 x 30 x 3.20mm MS SQ. TUBE |
| 8 | For Post | 80 x 80 x 3.2mm MS SQ. TUBE |
| 9 | Gap Between Tubes | 125mm |
| 10 | Bottom Rail on ground | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 11 | Bottom Rollers | Heavy Duty Bottom Wheel With both side Bearings |
| 12 | Guide Rollers supporter during Gate movement | Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate |
| 13 | Painting | Two Coats of Primer and Two coats of PU Paint |
| 14 | Motor | 100% Imported from Europe - BFT/Nice make |
| 15 | Safety | Photo sensors |
| 16 | Safety | Flashing Light |

**Boom Barrier**

| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Size | 8/6/4.5 Mtr |
| 2 | Make | Nice/BFT |
| 3 | Opening time | Opening Time- 8S/6S/4S |
| 4 | Motor Power Supply | 24V |
| 5 | Type of limit Switch | Electronic |
| 6 | Safety | Photocell sensor |
| 7 | Operated | Push Button Pedant |
| 8 | Movable support at other end considered | for 6 mtr and 8 Mtr Boom Barrier only |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | Remark |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | In Client Scope |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site | In Client Scope |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | In Client Scope |
| 4 | Any civil / masonry/structural work required | In Client Scope |
| 5 | All structure support required | In Client Scope |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | In Client Scope |
| 7 | Conduits, Cables required | In Client Scope |
| 8 | Lifting Equipements | In Client Scope |

**D) Terms & Conditions**

**Price** : Ex Works Chennai

**Delivery** : 5 weeks for Sliding Gate, Boom Barrier 6mtr and 4.5 mtr & 12 to 14 weeks for 8 mtr Boom barrier from confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 1) Supply - 30% Advance along with Confirmed Purchase Order and 70% Against Delivery.
2) Installation - 100% After Installation.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551096333
For NIHVA Technologies Pvt Ltd