NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1841 **Date : 20.07.2019**

Depa India Pvt Ltd
203 2nd Floor setellite silver,
Andheri –Kurla road.
Marol, Andheri East, Mumbai 400059.

Kind Attention : **Mr. Vinod Vishwakarma**
Email ID : Vinod.Vishwakarma@depa.com
Contact No : 77188 44490

Project Name And Location :

Subject : Quotation for 2 Hrs Fire Rated Rolling Shutter and Gear Operated Rolling Shutter.

Dear Sir

Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**2 Hrs. Fire Rated Motorized Rolling Shutters (BS476) -100% IMPORTED** **•Shutter Slats: Zinc coated steel solid slats** **•Slat Thickness: 1.0mm thick** **•Shutter Guide: Fabricated from hot-dipped galvanised steel of 3.0mm.** **•Operated by: Motor with one unit push button switch & manual override**				
1	Size : (W) 2400 mm x (H) 3000 mm **(Supply + Installation)**	4	No	220,000	880,000
2	Size : (W)1800 mm x (H) 3000 mm **(Supply + Installation)**	1	No	198,000	198,000
3	Size : (W) 2000 mm x (H) 3000 mm **(Supply + Installation)**	2	No	201,000	402,000
4	Size : (W) 3000 mm x (H) 3000 mm **(Supply + Installation)**	2	No	216,000	432,000
				Total	**1,912,000**
B	**Gear Operated Rolling Shutter** **Technical Specifications:** **• MS Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 3 mm Thick MS Guide** **• Hood Cover : 1.2 mm Thick GI material** **• Gear Assembly** **• With Painting** **(Supply + Installation)**				
1	**Size :** (W) 3000 mm x (H) 3000 mm	16	No	91,000	1,456,000
2	**Size :** (W) 3925 mm x (H) 3000 mm	13	No	104,000	1,352,000
				Total	2,808,000



GST Pune	**27AAECN0437H1ZM**

Total	**4,720,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra As applicable.
4	**Delivery**	:	8 -9 weeks for Fire Rated Rolling Shutter
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST @18% Extra
8	**Validity**	:	15 days from the date of quotation.
9	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Ravindra Kharat** on **7410169333** For any further Clarification in this concern

With Best Regards

Ulka Auti
7219206333
For Nihva Technologies Pvt Ltd