NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ARCAIDS
ARCHITECTURAL CONSULTANTS PVT. LTD.
305/6 M.P.J. Chambers, Wakdewadi,
Mumbai - Pune Road.,
PUNE 411 003

Date : 16.10.2019
Quote NO : SQT/19-20/2161
Kind Attn : Tejashree
Email Id : engineers@arcaids.com
Contact No: 20-25812399

Subject : Quotation for Rolling Shutter and Gate.(Project Loction - Chakan.)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	MS Motorized Rolling Shutter	4500	4500	1	143,000	143,000	20,000	20,000
2	MS Motorized Rolling Shutter	4000	5800	1	161,000	161,000	20,000	20,000
3	MS Motorized Rolling Shutter	3000	4500	1	107,000	107,000	20,000	20,000
4	MS Motorized Rolling Shutter (Perforated)	3000	4000	1	103,000	103,000	20,000	20,000
5	MS Motorized Rolling Shutter (Perforated)	3000	3300	1	93,000	93,000	20,000	20,000
6	Gear Operated Rolling Shutter	3000	4000	1	83,000	83,000	15,000	15,000
7	Gear Operated Rolling Shutter	3000	3000	1	68,000	68,000	15,000	15,000
8	Motorized Telescopic Sliding Gate	10000	2000	1	636,000	636,000	20,000	20,000
9	High Speed Door Rr 300+Alu	4000	4500	1	419,000	419,000	20,000	20,000
			Total			**1,813,000**		**170,000**
10	P&F Charges			3%		54,390		
	Total Without Taxes					1,867,390		170,000
	GST Extra @ 18%			18%		336,130.20		30,600
	Total With Taxes					**2,203,520**		**200,600**
11	Transportation Charges					In Client Scope		
12	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

MS Motorized Rolling Shutter

Sr .No.	Specification	MS Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

MS Gear Operated Rolling Shutter

Sr .No.	Specification	MS Gear Operated Rolling Shutter
1	Description:	Gear Operated Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h
10	Hood Cover	Made of GI Sheet Thickness 1.2 mm GF mm with 25x25x3mm angle stiffener
11	Surface finish	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat
12	Operation	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Albany Make Rapid Roll Up Door RR300+AL

Sr .No.	Specification	Albany Make Rapid Roll Up Door RR300+AL
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
4	Side Frames:	Aluminium profiles, anodised
5	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
7	Bottom beam:	Anodized extruded aluminium.
8	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
9	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd