**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Aditya Constructions**
Plot NO. 128, Flat No. 3, Usha Apt. ,Nr. Sadhu Vaswani Garden
Pimpri, 411017
Pune, Maharashtra

**Date :** 18.12.2020
**Quote NO :** SQT.20.21.2892
**Kind Attn :** Mr.Ashok
**Email Id :** adityaconstructionpune@gmail.com
**Contact No:** 9011042905

**Project Name & Location:** Kurkumbh MIDC

**Subject : Quotation for Motorised Rolling Shutter, Fire rated Rolling Shutter ,NIHVA make High Speed Door , Sliding Gate ,Retractable Dock Shelter , Boom Barrier , Bollards**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.**


| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2,3 |
| C. | General Conditions | 4 |
| D. | Terms & Condtions | 4 |


**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Length (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | GI Motorised Rolling Shutter- Internal | 3000 | 4000 | 1 | 145,000 | 145,000 | 20,000 | 20,000 |
| 2 | GI Motorised Rolling Shutter- Internal | 3000 | 3500 | 1 | 138,000 | 138,000 | 20,000 | 20,000 |
| 3 | GI Motorised Rolling Shutter- Internal | 3000 | 3000 | 1 | 130,000 | 130,000 | 20,000 | 20,000 |
| 4 | GI Motorised Rolling Shutter- Internal | 2500 | 3000 | 1 | 123,000 | 123,000 | 20,000 | 20,000 |
| 5 | GI Motorised Rolling Shutter- Internal | 2500 | 4000 | 1 | 135,000 | 135,000 | 20,000 | 20,000 |
| 6 | GI Motorised Rolling Shutter- Internal | 1800 | 3000 | 1 | 112,000 | 112,000 | 20,000 | 20,000 |
| 7 | GI Motorised Rolling Shutter- External | 3000 | 4000 | 1 | 155,000 | 155,000 | 20,000 | 20,000 |
| 8 | GI Motorised Rolling Shutter- External | 3000 | 3500 | 1 | 147,000 | 147,000 | 20,000 | 20,000 |
| 9 | GI Motorised Rolling Shutter- External | 3000 | 3000 | 1 | 140,000 | 140,000 | 20,000 | 20,000 |
| 10 | GI Motorised Rolling Shutter- External | 2500 | 3000 | 1 | 132,000 | 132,000 | 20,000 | 20,000 |
| 11 | Fire rated Rolling shutter | 3000 | 4000 | 1 | 261,000 | 261,000 | 20,000 | 20,000 |
| 12 | Fire rated Rolling shutter | 3000 | 3500 | 1 | 255,000 | 255,000 | 20,000 | 20,000 |
| 13 | Fire rated Rolling shutter | 3000 | 3000 | 1 | 249,000 | 249,000 | 20,000 | 20,000 |
| 14 | Fire rated Rolling shutter | 2500 | 3000 | 1 | 243,000 | 243,000 | 20,000 | 20,000 |
| 15 | Fire rated Rolling shutter | 1800 | 1800 | 1 | 238,000 | 238,000 | 20,000 | 20,000 |
| 16 | NIHVA Make High Speed Door | 3000 | 4000 | 1 | 328,000 | 328,000 | 20,000 | 20,000 |
| 17 | Single Leaf Motorised Sliding Gate | 10000 | 1500 | 1 | 396,000 | 396,000 | 20,000 | 20,000 |
| 18 | Wicket Gate | 1500 | 1500 | 1 | 40,000 | 40,000 | 10,000 | 10,000 |
| 19 | Retractable Dock Shelter | 3400 | 3500 | 6 | 140,000 | 840,000 | 15,000 | 90,000 |
| 20 | Boom Barrier | 6 Mtrs | | 4 | 121,000 | 484,000 | 15,000 | 60,000 |
| 21 | Fix Bollards | Dia 100 mm | 1000 Height | 30 | 8,000 | 240,000 | 3,000 | 90,000 |
| 22 | Additional accessories for High Speed Door | Radar Sensor | | 1 | 35,000 | 35,000 | | |
| | | Loop Detector | | 1 | 35,000 | 35,000 | | |
| | | Additional Push Button | | 1 | 5,500 | 5,500 | | |
| | | Flashing Light | | 1 | 7,500 | 7,500 | | |
| | | Interlocking Pull Switch | | 1 | 20,000 | 20,000 | | |
| | | Remote | | 1 | 9,500 | 9,500 | | |
| 23 | Additional accessories for Fire Rated Rolling Shutter | Key Switch | | 1 | 5,500 | 5,500 | | |
| | | Smoke Detector | | 1 | 24,000 | 24,000 | | |
| | | | | **Total** | | **5,073,000** | | **590,000** |
| 24 | | | P&F Charges | 3% | | **152,190** | | |
| | | | **Total Without Taxes** | | | **5,225,190** | | **590,000** |
| | | | GST Extra @ 18% | 18% | | 940,534 | | 106,200 |
| | | | **Total With Taxes** | | | **6,165,724** | | **696,200** |
| 25 | | | Transportation Charges | | | **Extra at Actual** | | |
| 26 | | | Unloading Charges @ Site | | | **In Client Scope** | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

## Motorized Rolling Shutter





| | | |
|---|---|---|
| **Sr .No.** | **Specification** | **GI Motorized Rolling Shutter** |
| 1 | **Description:** | Motorised Rolling Shutter with GI Laths with thickness of 1 mm. |
| 2 | **Mounting Location area** | Inside area / Outside area |
| 3 | **Mounting Surface** | On Concrete /Steel |
| 4 | **Curtain Panel** | The panel made of 1.0mm thick GI. |
| 5 | **Curtain panel size** | 75mm wide |
| 6 | **Curtain Profile** | Curved |
| 7 | **Bottom Profile** | M. S. Plate 100 mm x 2.5 mm thick with angle stiffener |
| 8 | **Side Guide Profile** | M.S." U" Shaped profile |
| 9 | **Roller Shaft** | M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h |
| 10 | **Side Brackets** | MS Plate 3 mm to 10 mm thick, as per the opening dimension. |
| 11 | **Hood Cover** | Made of GI Sheet Thickness 0.9 mm |
| 12 | **Surface finish** | Powder Coating |
| 13 | **Drive Unit & Mounting Type** | Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection |

## Retractable Dock Shelter

| **Sr. No** | **Description** | **Specifications** |
|---|---|---|
| **1** | **Size** | (W) 3400 mm x (H) 3500 mm |
| **2** | **Top Curtain** | 1000 mm |
| **3** | **Side Curtain** | 600 mm |
| **4** | **Curtain colour** | Black |
| **5** | **Parking Guides** | White, Yellow |
| **6** | **Wall Fixings** | Concrete, Sandwich light Concrete, Load house cavity, insulated panel |
| **7** | **Top & Side Curtaiins** | Double Layer High Quality Polyester |
| **8** | **Thickness** | 3.0 mm |
| **9** | **Weight** | Approx 3400 g/m2 |

## NIHVA Make High Speed Door

- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels



| **Sr. No** | **Description** | **NIHVA Make High Speed Door** |
|---|---|---|
| **1** | Use | Internal Door |
| **2** | Control Panel | 4 Push Button operated |
| **3** | Security Features | EN 13241-1 Standard |
| **4** | Resistance to wind load | EN12424 upto class 1 |
| **5** | Curtain | Fabric Transparent PVC section |
| **6** | Guide Material | Aluminum |
| **7** | Hood Cover | GI |
| **8** | Motor Cover | GI |
| **9** | Operator & Control | German Make Motor |
| **10** | Connecting Voltage | 220V , 1Ph , N |
| **11** | Open-Stop-Close Button | Standard |
| **12** | Protection Category | IP 54 / IP 65 |
| 13 | Power Consumption | 0.75 kw Motor |
| 14 | Emergency Off Button | Standard |
| 15 | Closing Zone Monitoring | Optical Safety edge |
| 16 | External Route Monitoring | Photocell |
| 17 | Emergency Opening | Crank Handle |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## Motorised Single Leaf Sliding Gate

| Sr .No. | Specification | Motorized Single Leaf Sliding Gate |
|---|---|---|
| 1 | **Door type** | Motorized Single Leaf Sliding Gate |
| 2 | **Opening Direction** | Horizontal - from left to right or reverse |
| 3 | **Mounting Location area** | Inside area |
| 4 | **Design Pattern** | Standard Tubular Design Pattern |
| 5 | **Outer Tube** | 100 x 100 x 3.6 mm THK SQ. TUBE |
| 6 | **For Post** | 100 x 100 x 3.6 mm THK SQ. TUBE |
| 7 | **Innear Tube** | 50 x 50 x 2.6 mm THK SQ. TUBE |
| 8 | **Gap Between Tubes** | 125mm |
| 9 | **Bottom Rail on ground** | dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams |
| 10 | **Bottom Rollers** | Heavy Duty Bottom Wheel With both side Bearings (chorme plated) |
| 11 | **Guide Rollers supporter during Gate** | Nylon Rollers with Bearings both side mounted on column for support smooth |
| 12 | **Painting** | 2 Coats of EPOXY polyamide based enamel finish of approved colour |
| 13 | **El motor make** | BFT – Italy (100% imported) |
| 14 | **Emergency Operation** | Manual after turn the switch |
| 15 | **Operating Switch** | Push Button from inside , Remote |
| 16 | **Safety** | Photocells, Flashing Light |

## Boom Barrier






| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Size | 6 Mtr |
| 2 | Make | Nice/BFT |
| 3 | Opening time | Opening Time- 6S |
| 4 | Motor Power Supply | 24V |
| 5 | Type of limit Switch | Electronic |
| 6 | Safety | Photocell sensor |
| 7 | Operated | Push Button Pedant |

## Bollards

| Sr. No. | Description | Specifications |
|---|---|---|
| 1 | Size | 100 mm Dia x 1000 mm Height |
| 2 | Make | Nihva |
| 3 | Material | MS |



**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description | |
|---|---|---|
| 1 | Secured and fully covered Store area to keep the material | |
| 2 | Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site | |
| 3 | Electrical Supply on the site single phase/three phase points at different places. | |
| 4 | Any civil / masonry/structural work required | |
| 5 | All structure support required | |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. | |
| 7 | Conduits, Cables required | |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 9-10 Weeks for High Speed door , Dock shelter,Fire Rated Rolling Shutter & 5-6 weeks for Rolling Shutter , Boom Barrier ,Sliding Gate and Bollards from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% along with confirmed purchase order & Balance before dispatch

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Pradeep Shinde
7219206333
For NIHVA Technologies Pvt Ltd