NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Wani Projects & Infra Pvt. Ltd.
Pune

Date : 25.07.2020
Quote NO : SQT.20.21.0029
Kind Attn : Mr. Pankaj Kathale
Email Id : pankaj@wanigroup.com
Contact No: 9689535673

Project Name & Location: Welspun

Subject : Quotation for Rolling Shutter, High Speed Door, Dock Shelter and Dock Leveller

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 to 4
C.	General Conditions	5
D.	Terms & Condtions	5

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	GI Gear Operated Rolling Shutter	3000	4500	0	92,000	-	20,000	-
2	GI Gear Operated Rolling Shutter	3500	4500	3	1,03,000	3,09,000	20,000	60,000
3	GI Gear Operated Rolling Shutter	4000	4500	0	1,13,000	-	20,000	-
4	GI Gear Operated Rolling Shutter	4500	4500	0	1,24,000	-	20,000	-
5	GI Motorised Rolling Shutter (Indirect drive)	2200	3000	0	78,000	-	20,000	-
6	GI Motorised Rolling Shutter (Indirect drive)	2200	3500	0	83,000	-	20,000	-
7	GI Motorised Rolling Shutter (Indirect drive)	3000	4200	2	1,13,000	2,26,000	20,000	40,000
8	Fire Rated Motorised Rolling Shutter	3000	3000	0	3,12,000	-	20,000	-
9	Fire Rated Motorised Rolling Shutter	3500	4000	1	3,59,000	3,59,000	20,000	20,000
10	Retractable Dock Shelter	3500	4200	2	1,54,000	3,08,000	20,000	40,000
11	High Speed Door	3000	3000	3	6,81,000	20,43,000	20,000	60,000
12	High Speed Door	3400	3500	2	6,28,000	12,56,000	20,000	40,000
13	Dock Leveller	2000	3000	2	2,15,000	4,30,000	20,000	40,000
				Total Value		**49,31,000**		**3,00,000**
				P&F Charges	3%	1,47,930		
				Total Without Taxes		**50,78,930**		**3,00,000**
				GST Extra @ 18%	18%	9,14,207		**54,000**
				Total With Taxes		**59,93,137**		**3,54,000**
				Total (Supply + Installation) with Taxes				**63,47,137**
14				Transportation Charges		**Extra at Actual**		
15				Unloading Charges @ Site		**IN Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

GI Rolling Shutter

Sr .No.	Specification	Description
1	Motorised Rolling Shutter	Gear Operated Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick GI.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of MS Sheet Thickness 0.9 mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Gear Operated	Gear Assembly

GI Rolling Shutter

Sr .No.	Specification	Description
1	Motorised Rolling Shutter	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick GI
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of MS Sheet Thickness 0.9 mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Indirect Drive, Electric Motor

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Fire Rated Rolling shutter

Sr .No.	Specification	SKB - BS476
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Model : SKB-G65 powder coated
3	**Bottom Bar**	Model : SKB-T120 powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal

Retractable Dock Shelter

Sr. No	Description	Specification
1	Size	(W) 3400 mm x (H) 3500 mm
2	Top Curtain	1000 mm
3	Side Curtain	600 mm
4	Curtain colour	Black
5	Parking Guides	White, Yellow
6	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
7	Top & Side Curtaiins	Double Layer High Quality Polyester
8	Thickness	3.0 mm
9	Weight	Approx 3400 g/m2

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

High Speed Door

Sr. No	Description	Details
1	Door panel:	Transparent PVC with Red (RAL 3002) reinforcement stripes.
2	Barrel:	Aluminium, anodized with shafts made of galvanized steel
3	Wind Reinforcement:	Door Panel wind tabs for improved wind resistance
4	Side Frames:	Aluminium profiles, anodised
5	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
6	Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.
7	Bottom beam:	Anodized extruded aluminium.
8	Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s
9	Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns

Dock Leveller

Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2000 mm x 3000 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Overall length	2000mm x 3000mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)3000 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Pair of Dock Bumper	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd