NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

B.G. Shirke Construction Technology pvt. ltd.
72-76 Mundhwa,
pune - 411036.

Date : 13.11.2019
Quote NO : SQT.19.20.2226R
Kind Attn : Anil Chougule.
Email Id : apchougule@shirke.co.in
Contact No: 8007992728

Project Name & Location: PIMPRI-CHINCHWAD NEW TOWN DEVELOPMENT AUTHORITY, AKURDI, PUNE-44.

Subject : Revised Quotation for Sliding Gate, Rolling Shutter and Boom Barrier.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**TELESCOPIC 2 LEAF SLIDING GATE (MOTORIZED)**	15000	1800	1	814,000	814,000	20,000	20,000
2	**TELESCOPIC 3 LEAF SLIDING GATE (MOTORIZED)**	15000	1800	1	857,000	857,000	20,000	20,000
3	**SINGLE LEAF SLIDING GATE (MOTORIZED)**	7500	1800	1	326,000	326,000	20,000	20,000
4	**TWO LEAF SWING GATE (MOTORIZED)**	6000	1800	1	308,000	308,000	20,000	20,000
5	**Gear Operated Rolling Shutter**	3000	3000	1	67,000	67,000	20,000	20,000
6	**Gear Operated Rolling Shutter**	2500	2500	1	54,000	54,000	20,000	20,000
7	**Boom Barrier**	3000		1	110,000	110,000	10,000	10,000
				Total		**2,536,000**		**80,000**
5	P&F Charges			3%		**76,080**		
	Total Without Taxes					**2,612,080**		**80,000**
	GST Extra @ 18%			18%		470,174		14,400
	Total With Taxes					**3,082,254**		**94,400**
6	Transportation Charges					**Included**		
7	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Specifications For 2 Leaf Telescopic Sliding Gate	Specifications For 3 Leaf Telescopic Sliding Gate
1	**Opening Direction**	Horizontal - from left to right or reverse	Horizontal - from left to right or reverse
2	**Mounting Location area**	Inside area	Inside area
3	**Design Pattern**	Standard Tubular Design Pattern	Standard Tubular Design Pattern
4	**Outer Frame Tube Sizes**	100 x 100 x 4mm MS SQ. TUBE	80 x 80 x 3.20mm MS SQ. TUBE
5	**Internal Vertical Tube Sizes**	38 x 38 x 3.20mm MS SQ. TUBE	38 x 38 x 3.20mm MS SQ. TUBE
6	**Gap Between Tubes**	125 MM	125 MM
7	**Bottom Rail on ground**	Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams	Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
8	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
9	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
10	**El motor make**	BFT – Italy (100% imported)	BFT – Italy (100% imported)
11	**Emergency Operation**	Manual after turn the switch	Manual after turn the switch
12	**Operating Switch**	Push Button from inside	Push Button from inside
13	**Safety**	Photocells	Photocells
14	**Metal Rack**	Zinc plated metal rack	Zinc plated metal rack

Sr. No	Description	Specifications For Single Leaf Sliding Gate	Specifications For 2 Leaf Swing Gate
1	**Opening Direction**	Horizontal - from left to right or reverse	Horizontal
3	**Design Pattern**	Standard Tubular Design Pattern	Standard Tubular Design Pattern
4	**Outer Frame Tube Sizes**	80x80x3.2mm MS SQ. TUBE	80 x 80 x 3.20mm MS SQ. TUBE
5	**Internal Vertical Tube Sizes**	40x40x2.6mm MS SQ. TUBE	40x40x2.6mm MS SQ. TUBE
6	**Gap Between Tubes**	125 MM	125 MM
7	**Bottom Rail on ground**	Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams	
8	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)	
9	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate	
10	**El motor make**	BFT – Italy (100% imported)	BFT – Italy (100% imported)
11	**Emergency Operation**	Manual after turn the switch	Manual after turn the switch
12	**Operating Switch**	Push Button from inside	Push Button from inside
13	**Safety**	Photocells	Photocells
14	**Metal Rack**	Zinc plated metal rack	Zinc plated metal rack

BOOM BARRIER

Each Boom Barrier Set include:
MICHELANGELO BT A Barrier-1No.
- **Round Boom First part-1No.**
- **Round Boom Second part- 1 No.**
- **Anchor Base- 1No.**
- **MOB. Boom Rest-1No.**
- **Rubber Safety Profile- 1No.**
- **OMEGA AT Acce. - 1No.**
- **Transmitter with Channels- 1No.**
- **Push Button**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Swapnil Kulat on 7219207333.**

With Best Regards
Ulka Auti
72519206333
For NIHVA Technologies Pvt Ltd