Oberoi Realty Limited

Commerz, 3rd Floor, Int'l Business Park,
Oberoi Garden City, Off W. E. Highway,Goregaon (E), Mumbai-400063
Tel : 02266773333 CIN:L45200MH1998PLC114818

WORK ORDER

PR No.	1011025414	PR Date	16.09.2025	W.O. No.	**4611023753**	W.O Date	22.04.2026

Please prepare challan / bill in the name of: **Oberoi Realty Limited**

Contractor:	**Nihva Technologies Private Limited**	Site:	**Elysian Tower B**
Address:	1st Floor, Above Renault show room Plot No. 187, G - Block, Thermax Chowk MIDC, Chinchwad, Pune Pune-411019	Address:	International Business Park Oberoi Garden City Off Western Express Highway Mumbai-400063
Contact: Tel:	Vijay Tarak 020-66304033 Mobile: 8551093333	Contact: Tel:	02266773333 Mobile :
PAN :	AAECN0437H GSTIN 27AAECN0437H1ZM	PAN:	AABCK0235H GSTIN 27AABCK0235H1ZW

Sr. No.	Work Description with Specification	Unit	Qty	Rate	Amount (INR)
00010.	**Retractable Roof Work Tower B** **HSN/SAC:995471 : Glazing services**	**AU**	**1.000**	**1,450,000.00**	**1,450,000.00**
1)	D/I/T/C AUTOMATIC SLIDING & FOLDING ROOF Design, Supply, Installation, Testing, Commissioning (DSITC) and Handing Over of Automatic Retractable Roof to the Employer complete in all respect, including but not limited to following : 1.1) Design and Engineering 1.1.1) Structural and architectural design as per approved drawings. 1.1.2) Design to accommodate the following unfactored loads: a) Self weight b) Live Load: 1.5 kN/m² c) Wind Load: 2.6 kN/m² 1.1.3) Submission of complete design documentation including: a) Structural calculations b) Material specifications c) Load assessments d) Connection details 1.1.4) Third party structural stability certificate from an independent qualified consultant. 1.1.5) Compliance with relevant codes, standards, and statutory requirements. 1.1.6) No fabrication or installation to commence without Employer' s written approval of design and certification. 1.2) Material and System Specifications 1.2.1) Roofing Sheet: Polycarbonate Compact Clear / Embossed, 3.0 mm thick or as required as per design. 1.2.2) Frame: Powder Coated MS and Aluminium Profile (AkzoNobel RAL Shade 9006) (Minimum DFT 70 to 80 micron). 1.2.3) Guide System: Anodized Aluminium Guide. 1.2.4) Interlocking Mechanism: Integrated for weather tight sealing. 1.2.5) Motorized Operation: a) Motor Type: Single Phase Bi directional Motor / as required as per design b) Speed: 09 to 12 m/min c) Power: As per roof dimensions d) Mechanical limit switch e) Rack and pinion arrangement f) Control panel with push button operation from inside and outside 1.2.6) Sealing: EPDM gaskets and sealants. 1.2.7) Drainage: Built in provision for water management. 1.2.8) Supply of Fireman' s Axe. 1.2.9) Fire alarm sensor integrated with motor. 1.3) Installation and Commissioning	NOS	1.000	1,450,000.00	1,450,000.00
		Total (INR) :			**1,450,000.00**

Approved By: Rupesh Rawal; Place: Mumbai; Date: 27-04-2026

Oberoi Realty Limited

Commerz, 3rd Floor, Int'l Business Park,
Oberoi Garden City, Off W. E. Highway,Goregaon (E), Mumbai-400063
Tel : 02266773333 CIN:L45200MH1998PLC114818

WORK ORDER

PR No.	1011025414	PR Date	16.09.2025	W.O. No.	**4611023753**	W.O Date	22.04.2026

Please prepare challan / bill in the name of: **Oberoi Realty Limited**

Contractor:	**Nihva Technologies Private Limited**	Site:	**Elysian Tower B**
Address:	1st Floor, Above Renault show room Plot No. 187, G - Block, Thermax Chowk MIDC, Chinchwad, Pune Pune-411019	Address:	International Business Park Oberoi Garden City Off Western Express Highway Mumbai-400063
Contact: Tel:	Vijay Tarak 020-66304033 Mobile: 8551093333	Contact: Tel:	02266773333 Mobile :
PAN :	AAECN0437H GSTIN 27AAECN0437H1ZM	PAN:	AABCK0235H GSTIN 27AABCK0235H1ZW

Sr. No.	Work Description with Specification	Unit	Qty	Rate	Amount (INR)
	1.3.1) Complete installation, alignment, testing, and commissioning of the retractable roof system. 1.3.2) Submission of operation manuals, warranty certificates, and as built drawings. 1.4) Training 1.4.1) Contractor to provide training after handing over of the works to Employer and Project Management Services (PMS) team appointed by Employer separately. 1.5) Scope of Work includes but not limited to following 1.5.1)Packing, loading, forwarding, transportation of materials to site, unloading and lifting of materials at site. 1.5.2) Submission of Third Party Design Certification. 1.5.3) Mathadi charges. Clear Opening Size (Plan Area) : 3400 mm X 2000 mm				
		Total (INR) :			**1,450,000.00**

Approved By: Rupesh Rawal; Place: Mumbai; Date: 27-04-2026

Oberoi Realty Limited

Commerz, 3rd Floor, Int'l Business Park,
Oberoi Garden City, Off W. E. Highway,Goregaon (E), Mumbai-400063
Tel : 02266773333 CIN:L45200MH1998PLC114818

WORK ORDER

PR No.	1011025414	PR Date	16.09.2025	W.O. No.	**4611023753**	W.O Date	22.04.2026

Please prepare challan / bill in the name of: **Oberoi Realty Limited**

			Amount (INR)
*	**IN: Central GST - ND@9.000 %**		**130,500.00**
*	**IN: State GST - ND@9.000 %**		**130,500.00**
		Grand Total (INR) R/ off:	**1,711,000**
Payment Terms :	15 days after receipt of invoice at Head office	**Amount in Words (INR) :**	Seventeen Lakh Eleven Thousand Only

Work to Start : 27.04.2026 **Work to Complete :** 31.07.2026

Vendor is required to submit their invoice through Nimble S2P supplier portal only. Link is https://sp-orl.nimbles2p.com/login/
General Terms and Conditions:

1)Unsigned Purchase Order/Work Order would not be valid and binding on the company.
2)Along with each current invoice,vendor shall submit the copy/ies of ESIC,PF,etc.as applicable for the preceding month/s OR on payment of such liabilites whichever is earlier.
3)Employer reserves the right to uphold the bill payment of the Vendor in the event of the Vendor fails to upload the correct GST returns for enabling the Employer to avail the credit.
4)HSN/SAC on the tax invoice shall match with corresponding HSN/SAC of the line item of the Work Order.
5)We will be deducting TDS u/s. 194Q of the Income Tax Act (the Act) w.e.f. 01st July 2021 @0.1% on the aggregate value of goods purchased from you exceeding Rs. 50 lakhs during the financial year 2021-22, if any. Therefore, you are requested not to collect TCS u/s. 206C (1H) of the Act.
6)If you are a #Specified person" u/s. 206AB of the Act as per the report received from the Income Tax Department, we will be deducting TDS at higher rate as specified u/s. 206AB of the Act

Design and SITC of Retractable Roof

CN NO.:ORL/Elysian Tower B/CONT/CN-Fresh Orders/2026-27/0008

Approved By: Rupesh Rawal; Place: Mumbai; Date: 27-04-2026